

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 14 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Hayes of Alpine Oil & Royalty Co. has this date requested permission to plug the following described well:

Mr. Hayes guarantees payment of the plugging fee.

Operator's full Name: Alpine Oil & Royalty Co.

Complete Address: 800 Bitting Bldg. Wichita, Ks.

Lease Name: August Schonhaler Well No. A 2

Location: C-- SW/4 Sec. 30 Twp. 10 Rge. 19 (E)(W) X

County: Rooks Total Depth 3855 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hayes was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace
 70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and
 displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
 plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole ~~with 2~~
 with 2 sc cement.

Very truly yours,

Leo F. Massey
 Conservation Division Agent