

15-163-00339-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Rooks County, Sec. 27 Twp. 10 Rge. 19 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SW  
Lease Owner C-G DRILLING CO.  
Lease Name O'BRIEN Well No. # 1  
Office Address 206 Union National Bank Bldg.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 12 19 51  
Application for plugging filed July 12 19 51  
Application for plugging approved July 12 19 51  
Plugging commenced July 12 19 51  
Plugging completed July 12 19 51  
Reason for abandonment of well or producing formation too low structurally



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Great Bend, Kas  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8" (25.55#)	190.39'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with drilling mud to 192'. Drove plug to 190'. Put in 15 sacks cement then pumped full of mud 25' from top of hole. Drove plug down to 25' then filled to top with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to C-G Drilling Co.  
Address 206 Union National Bank Bldg, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
R. A. COOK (Employee or owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. A. Cook  
206 Union National Bank Bldg.  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of July, 1951.


August 11, 1954

Notary Public

28-3273-s 4-50-10M

PLUGGING  
SEC 27 T10 R19  
BOOK PAGE 460 1

7-18-51  
JUL 18 1951  
CONSERVATION DIVISION  
Wichita, Kansas



15-163-00339-0000

CONTRACTOR'S WELL LOG

Operator C-G Drilling Co. Farm Name O'Brien #1

Location NW NW SW Sec. 27-10-19W

Pool Name W. C. County Rooks, State Kansas

Commencement Date 6-30-51 Completion Date 7-12-51

LOG OF WELL

Elevation 2186 R. B.  
All Measurements from the top of rotary bushing.

DEPTH		FORMATION	DEVIATION FROM VERTICAL	REMARKS
FROM	TO			
0	190			
190	470	Shale		
470	1025	Shale-Sand		
1025	1235	Sand		
1235	1330	Shale		
1330	1535	Shale	1500-0°	
1535	1575	Anhydrite		
1575	1650	Shale		
1650	1860	Shale		
1860	2040	Shale	2000-0°	
2040	2180	Lime-Shale		
2180	2245	Lime-Shale		
2245	2365	Lime-Shale		
2365	2460	Lime-Shale		
2460	2485	Lime-Shale	2500-0°	
2485	2645	Lime-Shale		
2645	2740	Lime-Shale		
2740	2800	Lime-Shale		
2800	2865	Lime-Shale		
2865	2930	Lime-Shale		
2930	3025	Lime-Shale	3000-0°	
3025	3130	Lime-Shale		
3130	3190	Lime-Shale		
3190	3245	Lime-Shale		
3245	3286	Lime		
3286	3315	Lime		
3315	3370	Lime-Shale		
3370	3390	Lime-Shale		
3390	3440	Lime		
3440	3471	Lime		
3471	3505	Lime	3500-0°	
3505	3550	Lime		
3550	3595	Lime		
3595	3635	Lime-Shale		
3635	3685	Lime-Shale		
3685	3714	Congl.		
3714	3741	P.D.		

CASING LEFT IN WELL AFTER COMPLETION

Log 190-395 (9 Jts.) 8 5/8" OD Casing

STATE OF KANSAS, COUNTY OF SEDGWICK) SS

The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

**PLUGGING**  
WELL SEC 27 T 10 R 19W  
BOOK PAGE 96 LINE 1

**RECEIVED**  
JUL 18 1951  
C-G DRILLING CO.

Witness my hand and seal as President

Subscribed and sworn to before me this 17th day of July, 1951  
My commission expires August 11, 1954

Notary Public