

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-23,231-0000

LEASE NAME Largent-Dick

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 4

660 Ft. from ^N Section Line

1,650 Ft. from E Section Line

SEC. 29 TWP. 10 RGE. 19 (E or W)

COUNTY Rooks

LEASE OPERATOR Ash-Bie Oil Co.

ADDRESS PO Box 194, Ellis, KS. 67637

PHONE#(913) 726-3663 OPERATORS LICENSE NO. 4026

Date Well Completed 9-3-93

Character of Well D & A

Plugging Commenced 9-3-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-3-93

The plugging proposal was approved on 9-3-93 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3,791'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	225'	Cmtd. w/165 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Push bridge plug to 3,758', spot 25 sax cement on plug thru drill pipe, push bridge plug to 1,645', spot 25 sax cement on plug thru drill pipe. Push bridge plug to 940', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 275', spot 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug, 15 sax cement down rat hole and 10 sax cement down mouse hole.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 160

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ash-Bie Oil Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman Contractor (Employee of ~~Operator~~) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman RECEIVED

(Address) Shields Bldg., Russell, KS. 67665 STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 15th day of September 16, 1993

Ruth Phillips Notary Public
9-16-93
CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires: _____





Shields


15-163-23231-0000

Russell, Kansas

WELL LOG

Operator: Ash-Bie Oil Company
 Well: Largent-Dick #4
 Commenced: August 26, 1993
 Completed: September 3, 1993
 Contractor: Shields Drilling Co.

Well Description: C E/2 NW NE
 Sec. 29-10S-19W
 Rooks County, KS.



CASING RECORD

Size	Run	Pulled
8 5/8"	225'	Cmtd. w/165 sax

Elevation: 2,218' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Lime streaks, sand & shale	228'
Shale	414'
Shale & sand	1,627'
Anhydrite	1,659'
Shale	2,363'
Shale & lime	3,441'
Lime	3,791' RTD

Notes

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1993

CONSERVATION DIVISION
Wichita, Kansas