

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

ROOKS County. Sec. 29 Twp. 10 Rge. 19W (X)(W)

Location as "NE/CNW/SW" or footage from lines SW NW NE

Lease Owner PETROLEUM, INC.

Lease Name DICK Well No. 2

Office Address ROUTE 2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed JANUARY 1, 19 54

Application for plugging filed APRIL 14, 19 59

Application for plugging approved APRIL 15, 19 59

Plugging commenced JULY 1, 19 59

Plugging completed JULY 5, 19 59

Reason for abandonment of well or producing formation DEPLETION OF
PRODUCEABLE ZONES.

If a producing well is abandoned, date of last production FEBRUARY 22, 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY, BOX 326, HAYS, KANSAS.

Producing formation ARBUCKLE Depth to top 3766 Bottom --- Total Depth of Well 3772 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	262'	NONE
				5-1/2"	3768'	NONE
ARBUCKLE	WATER & LITTLE OIL.	3768'	3772'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

GLOBE OILWELL CEMENTING COMPANY PUMPED IN 40 SACKS COMMERCIAL GEL AT 3772', FOLLOWED BY PLUG. PLACED 70 SACKS CEMENT ON TOP OF PLUG, TO 1316, PUMPED IN 8 SACKS COMMERCIAL GEL FROM 1316' TO 550', PLACED 62 SACKS CEMENT FROM 550' TO BASE OF WELL CELLAR.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GLOBE OILWELL CEMENTING COMPANY

Address BOX 628, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.

DON SEARLE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

ROUTE 2, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 9TH day of JULY, 1959

My commission expires APRIL 14, 1963

RE
STATE CORP
JUL 17 1959
7-17-59
CONSERVATION DIVISION
Wichita, Kansas

Arthur J. Nile Notary Public.

PLUGGING
FILE SEC. 29 T. 10 R. 19W
BOOK PAGE 30 LINE 20

DRILLER'S LOG DICK #2

Petroleum, Inc., Operator

Section 29, Twp. 10S, Rge. 19W

Garvey Drilling Company, Contractor

Location: SW NW NE

Drilling Commenced: December 30, 1953.

County: Rooks County, Kansas

Drilling Completed: January 9, 1954.

Production: Arbuckle

Casing Record: 8-5/8" @ 262' w/135 sax.
5-1/2" @ 3768' w/75 sax.

R.T.D.: 3772'

Figures below indicate bottom of formation:

20	Surface Clay & Rock
245	Sand & Sandy Shale
262	Shale
810	Shale & Shells
940	Sand
1110	Shale & Shells
1320	Sand
1607	Shale, Shells & Red Bed
1649	Anhydrite
2080	Shale & Shells
2865	Lime & Shale
3005	Shale & Lime Shells
3105	Shale & Shells
3197	Lime & Shale
3268	Lime & Shale Breaks
3370	Lime & Shale
3681	Lime
3692	Shale
3740	Conglomerate
3764	Shale
3772	Lime
3772	R.T.D.

Tops:

Heebner:	3407 (-1193)
Toronto:	3433 (-1219)
Lansing:	3448 (-1234)
Conglomerate:	3695 (-1481)
Simpson:	3728 (-1514)
Arbuckle:	3766 (-1552)

REC
STATE CORP.

JUL 17 1954

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W.W. Fisher

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 20th day of January, 1954.

Charles H. Therman
Notary Public

My commission expires: October 13, 1954.

FILING			
FILE	SEC	291	10 R 19W
BOOK	PAGE	30	LINE 20