


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 29 Twp. 10S Rge. (X) 29 (W)

Location as "NE/CNW/SW" or footage from lines NE NW NW  
Lease Owner Rains & Williamson Oil Co.  
Lease Name LARGENT-DICK Well No. 1  
Office Address 412 Union Center - Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-3- 19 63  
Application for plugging filed 3-3 19 63  
Application for plugging approved 3-3 19 63  
Plugging commenced 3-3 19 63  
Plugging completed 3-3 19 63  
Reason for abandonment of well or producing formation No oil or gas found in commercial quantities

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production ----- 19 --  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty - Hays, Kansas  
Producing formation ----- Depth to top --- Bottom --- Total Depth of Well 3826 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	235.04'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set first plug at 540'. Cemented through drill pipe with 20 sacks cement. Filled hole with rotary mud to 240'. Set second plug at 240' and cemented with 20 sacks of cement through drill pipe. Filled hole to 40' of base of cellar with rotary mud and cemented with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
3-7-63  
MAR 7 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.  
Address 412 Union Center - Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Wilson Rains - Partner (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains  
412 Union Center - Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of March, 1963

My commission expires November 8, 1966

Sherry Gish  
Sherry Gish Notary Public.



ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co.  
NO. 1 LARGENT-DICK  
NE NW NW Sec. 29-10S-19W  
Rooks County, Kansas

Contractor: Rains & Williamson  
Oil Co.  
Commenced: 2-22-63  
Completed: 3-3-63

Remarks: Set 8-5/8"  
casing at 243' with  
130 sacks quick  
cement

FORMATIONS

Sand and Blue Shale	241'
Shale	655'
Shale and Shells	1020'
Sand and Shale	1275'
Shale & Red Beds	1475'
Shale and Shells	1610'
Anhydrite	1638'
Shale and Shells	2140'
Lime and Shale	2265'
Shale and Lime	2430'
Lime and Shale	3160'
Shale	3206'
Lime	3825'
Rotary Total Depth (D & A)	3825'

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
Wilson Rains  
Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 6th day of March, 1963.

*Sherry Gish*  
Sherry Gish Notary Public

My Commission Expires:  
November 8, 1966

RECEIVED  
STATE CORPORATION COMMISSION

MAR 7 1963

CONSERVATION DIVISION  
Wichita, Kansas

