


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County. Sec. 29 Twp. 10 S Rge. (E) 19 (W)
Location as "NE/CNW/SE" or footage from lines SE SW SE
Lease Owner Clinton Oil Company
Lease Name Ruth Largent #1V Well No. 1-V
Office Address P. O. Box 1201, Wichita, Kansas 67201
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 7-24 1971
Application for plugging filed 12-17 1973
Application for plugging approved 12-19 1973
Plugging commenced 1/5/74 1974
Plugging completed 1/16/74 1974
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 12-21 1973
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation LKC Depth to top 3481 Bottom 3484 Total Depth of Well 3768 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	254	none
				5 1/2"	36 3764	202 2620'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, pushed plug to 3400' and ran 10' sand and dumped 4 sacks cement. Loaded hole, shot pipe at 2622', pulled pipe. Squeezed well with 5 sacks hulls, 35 sacks gel and 120 sacks pos with 6% gel.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1974

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor ~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~ KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 1974

My commission expires

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1973
CONSERVATION DIVISION
Wichita, Kansas

RUTH M. LARGENT #1
SE SW SE, Sec. 29-10S-19W
Rooks County, Kansas

Commenced: June 28, 1971
Completed: July 8, 1971

OPERATOR: Clinton Oil Company

DEPTH		FORMATION	REMARKS
From	To		
0	95	Surface Clay & rocks & sand	Ran 7 joints of new 20#
95	256	Sand and Shale	8 5/8" csg set @ 254'
256	735	Shale and Sand	w/185 sx common cement.
735	1489	Lime, Shale, Sand	P.D. 7 PM 6/28/1971
1489	1586	Shale and Redbed	Cement Cir. Job by Sun
1586	1625	Anhydrite	
1625	1733	Shale	
1733	2005	Shale and Lime	
2005	3187	Lime and Shale	
3187	3517	Lime	
3517	3582	Lime and Shale	
3582	3712	Lime	
3712	3765	Lime-Shale-Conglomerate	
3765	3768	Lime-Conglomerate	Ran 119 jts of 14# new
3768	TD		5 1/2" csg set @ 3764 w/ 175 sks. Deras-tuff fiber 1/8# per sack P.D. @ 5:30 PM 7/8/71 Job by Halliburton


I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the SE SW SE, Sec. 29-10S-19W, Rooks County, Kansas to the best of my knowledge and belief.

James S. Sutton II
James S. Sutton II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 14th day of July, 1971, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.



My commission expires November 29, 1971

Marjorie Hall
Marjorie Hall, Notary Public