

LEASE NAME Keller "B"

WELL NUMBER 1

330 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 30 TWP. 10 SRGE. 19 (X or W)

COUNTY Rooks

Date Well Completed 9-29-80

Plugging Commenced 7-30-92

Plugging Completed 7-30-92

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 605, Russell, KS 67665

PHONE 913 ) 625-6374 OPERATORS LICENSE NO. 3456

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-30-92 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation L-KC Depth to Top 3234 Bottom 3546 T.D. 3780

Show depth and thickness of all water, oil and gas formations.

*27  
KCC*

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC	Oil & Water	3234	3546	8 5/8"	256	None
				4 1/2"	3780	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set.  
Perforated 3 holes at 1630' & 940'. Ran tubing to 3690' spotted 100 sx. 60/40 Poz, 10% gel & 1/4# flo-seal & 2 sxs. hulls. Pulled to 1500' & circulated to surface w/75 sx. & 2 hulls - same cement. Pulled tubing. Hooked to 4 1/2" casing - 100 sx. same w/1 hull - max. 800#. SIP-300#. Hooked to 8 5/8" & pumped 75 sx. same. Max. -  
 (If additional description is necessary, use BACK of this form.) 600#, SIP-200#

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Russell, KS 67665

RECEIVED  
 STATE CORPORATION COMMISSION  
 8-12-92  
 AUG 12 1992

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy, Inc.

STATE OF Kansas COUNTY OF Russell, ss.

CONSERVATION DIVISION  
 Wichita, Kansas

Terry W. Piesker (Employee of Operator AFG Energy, Inc.) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 605, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 10th day of August, 19 92

Pamela K. Steckel  
 Notary Public

My Commission Expires: 11-19-92

