

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-22713-0000

LEASE NAME Keller #

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

3630 Ft. from S Section Line

990 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Company, Inc.

SEC. 30 TWP. 10S RGE. 19W (E) or (W)

ADDRESS 250 N. Water, Suite 300 Wichita, KS 67202

COUNTY Rooks

PHONE#(913) 674-2103 OPERATORS LICENSE NO. 30606

Date Well Completed 8/1/85

Character of Well oil

Plugging Commenced 6/22/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/22/94

The plugging proposal was approved on 6/22/94 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? _____

Producing Formation LKC Depth to Top 3546 Bottom 3788 T.D. 3793 CTBP

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	Oil & Water	3546	3788			
				8 5/8	850	0
				5 1/2	3839	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perforated 5 1/2" csg @ 2250', salt section, 1600 Anhydrite & 200'. Pumped 225 sx 60/40 Poz, 10% gel, 1/4 # flocele & 300# hulls dwn 5 1/2" csg. Max press 500 psig, ISIP 200 psig. Hooked up to 8 5/8, topped off w/25 sx cement. Max press 200 psig, held.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address Hays, Kans

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Co. RECEIVED STATE CORPORATION COMMISSION 6-27-94 JUN 27 1994


STATE OF Kansas COUNTY OF Graham, ss.

John Gerstner (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) John Gerstner

(Address) Hill City, Ks



SWORN TO before me this 24 day of June, 19 94

Donna Gerstner
 Notary Public

My Commission Expires: 6/24/97