

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-20,069-0000

LEASE NAME SCHONTHALER

WELL NUMBER 1

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 30 TWP. 10S RGE. 19 (E) or (W)

COUNTY ROOKS

Date Well Completed 11/9/67

Plugging Commenced 1/7/97

Plugging Completed 1/8/97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Manta Petroleum, Inc.

ADDRESS P.O. BOX 4491, Englewood, CO 80155

PHONE # (303) 799-9828, x.152 OPERATORS LICENSE NO. 31638

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/29/96 (date)

by d David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? NO if not, is well log attached? YES

Producing Formation L/KC, Congl. Depth to Top 3,492 Bottom 3,723 T.D. 3,781

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
L/KC	OIL	3,458	3,684	8 5/8"	207'	0'
Conglomerate	OIL	3,700	3,746	5 1/2"	3,750'	0'
						4-11-97

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:
PERF. @ 615'-890'. TRIED TO K/O C.I.B.P. @ 2960' / MOVED PLUG SLIGHTLY. MIX 275 sx. CEMENT (10% GEL) w/450 # HULLS @ 450 # MAX P.S.I. SHUT IN @ 50 #. MIX 50 sx. CEMENT w/ 50 # HULLS. PUMP IN 8.5/8" BACKSIDE @ 600 # MAX. P.S.I. SHUT IN AT 500 #.

Name of Plugging Contractor Allied License No. _____

Address 24 Lincoln / 332 W. Wichita; P.O. BOX 31; Russell, KS 67665-0031

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Manta Petroleum, Inc.

STATE OF Colorado COUNTY OF ARAPAHOE, ss.

STEVE BECKLEY (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) _____

(Address) P.O. Box 4491, Englewood CO 80155

SUBSCRIBED AND SWORN TO before me this 8th day of April, 19 97

Tanya R. Voris TANYA R. VORIS
 Notary Public

My Commission Expires: 10-4-98

