

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 30 Twp. 10S Rge. (E) 19(W)  
Location as "NE/CNW\*SW\*" or footage from lines. NW/4 NW/4 SW/4  
Lease Owner Martin Oil Company, et al  
Lease Name Schoenthaler Well No. 1  
Office Address 527 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 18, 1956  
Application for plugging filed (verbal) October 18, 1956  
Application for plugging approved (verbal) October 18, 1956  
Plugging commenced October 18, 1956  
Plugging completed October 18, 1956  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3779 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None	None	0	207'	8 5/8"	203'	None
No oil string - D & A						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 200', set bottom plug at 200' with 15 sacks cement and 1/2 sack Hulls.

Filled hole with heavy mud to 40', set top plug at 40' with 10 sacks cement and 1/2 sack Hulls.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 26 1956  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Walters Drilling Co.  
Address 510 Orpheum Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Robert F. Walters (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters  
510 Orpheum Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of October, 1956

Pauline Henderson  
Notary Public.

My commission expires March 10, 1960

PLUGGING  
FILE SEC 30 T 10 R 19W  
BOOK PAGE 109 LINE 15

SCHONTHALER NO. 1

RT  
KCC

LOCATION: NW/4 NW/4 SW/4 Sec. 30-10S-19W, Rooks County, Kansas Date Spudded: 10-7-56

OPERATOR: Martin Oil Company Completion: 10-18-56

CONTRACTOR: Walters Drilling Co. Elevation: 2205 Gr  
2207 DF  
2210 KB

SURFACE CASING: 8 5/8" set at 207' with 150 sacks cement and 2 Gal. Chloride

OIL STRING: None. D & A

L O G

(Figures indicate bottom of formation)

Surface	0 to 207
Shale and Shells	1085
Sand	1325
Shale and Shells	1603
Anhydrite	1644
Shale and Shells	2335
Shale and Lime	3488
Lime	3779
Total Depth	3779

RECEIVED  
 OCT 23 1956  
 COMPTON  
 DIVISION  
 WALSHE, KANSAS

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

By

*Robert F. Walters*

Subscribed and sworn to before me this 23rd day of October, 1956

*Pauline Henderson*  
Notary Public

My commission expires:  
March 10, 1960

PLUGGING  
 FILE SEC. 30 T. 10 R. 19W  
 BOOK PAGE 109 LINE 15