

15-163-00670-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 30 Twp. 10S Rge. (E) 20 (W)

Location as "NE/CNW*SW*" or footage from lines 330' WEL & 990' NSL
Lease Owner Operator & Pt. Owner: Birmingham-Bartlett Drilling Co.
Lease Name Kelley Well No. 3
Office Address 300 Kaufman Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 16 19 54
Application for plugging filed (Verbal approval rec'd 5-16) May 18 19 54
Application for plugging approved " " " ") 19
Plugging commenced May 16 19 54
Plugging completed May 16 19 54
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production -- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Arbuckle Depth to top 3759' Bottom 3795' Total Depth of Well 3795 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & Shale		0	162	8-5/8"	167'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug set at 155' w/1/2 sacks hulls and 15 sacks cement mixed & poured.
Top plug set at 45' with 1/2 sack hulls and 10 sacks cement.

REC
STATE CORPORATION COMMISSION
5-19-54
MAY 19 1954
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Birmingham-Bartlett Drilling Co.
Address (Given above)

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Richard Hindery, partner of operator & part-lease owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BIRMINGHAM-BARTLETT DRILLING CO.


(Signature) By Richard Hindery, Partner
300 Kaufman Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 18th day of May, 1954.

Vivian F. Yinger
Notary Public.

My commission expires November 29, 1954.

PLUGGING
FILE SEC 30 T 10 R 190
BOOK PAGE 35 LINE 1



15-163-00670-0000

KELLER #3 WELL

LOCATION: ~~NE 1/4~~ SE 1/4 NE 1/4 30-108-20W
 Woods County, Kansas

SPUDED: 5--5-54

OPERATOR & CONTRACTOR: Birmingham-Bartlett Drilling Co.
 300 Kaufman Bldg., Wichita 2, Kansas

COMPLETED: 5-17-54

SURFACE CASING: 8-5/8" ~~2 1/2"~~ surface casing cemented
 at 162' with 130 sacks & 2 c.c. Plug
 pumped to 150'; plug down 9:45 PM 5-5-54

OIL STRING: None Run - Dry, Abandoned & Plugged

L O G

(Figures indicate bottom of formation)

0 -	162	Sand & Shale
	670	Shale
	762	Shale & Shells
	823	Sand & Shale
	1035	Shale & Shells
	1275	Sand
	1579	Shale & Sand
	1614	Anhydrite
	2055	Shale & Shells
	2270	Shale & Lime
	2560	Broken Lime
	2730	Lime & Shale
	2975	Shale & Shells
	3240	Lime & Shale
	3720	Lime
	3754	Conglomerate
	3765	Lime
	3771	Art buckle
	3795	Lime
	3795	RTD

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the Keller #3 Well, as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery
Partner

Subscribed and sworn to before me this 18th day of May, 1954.

Vivian F. Yinger
Vivian F. Yinger, Notary Public

My commission expires November 29, 1954.

STATE CORPORATION COMMISSION

MAY 19 1954

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
WELL No. 30 T 10 R 19W
BOOK PAGE 35 LINE 1