

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5420
Name: White & Ellis Drilling, Inc.
Address 1: P.O. Box 48848
Address 2: _____
City: Wichita State: KS Zip: 67201 + 8848
Contact Person: Dallas Flowers
Phone: (316) 321-0550

API No. ~~45~~ - 15-185-20-718 - 0000
If pre 1967, supply original completion date: _____
Spot Description: C NE SW
_____ Sec. 26 Twp. 25 S. R. 15 East West
3,300 Feet from North / South Line of Section
1,980 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stafford
Lease Name: Waddle Well #: 1

Check One: ~~Oil Well~~ Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: D-10,524 ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 292' Cemented with: 200 Sacks
Production Casing Size: 4 1/2" Set at: 4350' Cemented with: 125 Sacks

KCC
is
well
done
goes to
2

List (ALL) Perforations and Bridge Plug Sets:
Perfs 4268' to 4272'

Elevation: 2009 (G.L. / K.B.) T.D.: 4562 PBDT: 4320 Anhydrite Depth: N/A
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

as required

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

KANSAS CORPORATION COMMISSION

AUG 13 2009

RECEIVED

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Dallas Flowers

Address: P.O. Box 249 City: El Dorado State: KS Zip: 67042 + _____

Phone: (316) 321-0550

Plugging Contractor License #: 31627 Name: White Tail Crude Inc.

Address 1: P.O. Box 544 Address 2: _____

City: Ness City State: KS Zip: 67560 + _____

Phone: (785) 798-5116

Proposed Date of Plugging (if known): 09-14-09

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8-11-09 Authorized Operator / Agent: Dallas Flowers
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dist 1
PKT

WHITE & ELLIS OIL & GAS, INC.
BOX 448, EL DORADO, KS.

#1 WADDLE

26-25-15W
C NE SW

CONTR D.R. LAUCK

CTY STAFFORD

GEOL BILL SLADEK

FIELD WC (1/4 SW OF HAYNES EAST; SEP BY DRY HOLES)

E 2009 KB CM 3/28/77 CARD ISSUED 10/6/77 IF E 25 80 + 100 BW +
70 MCFGPD
MISS 4268-72

+	+	+
+	+	+
+	+	+

API 15-185-20,718

LOG	TOP	DEPTH	DATUM
RED FLAG	2725	-216	
STOTLER	3021	-1012	
HOW	3225	-1216	
OH	3544	-1535	
BEER	3661	-1652	
TBR	3698	-1669	
BR LM	3803	-1794	
LEANS	3825	-1816	
RRK	4110	-2101	
MISS	4267	-2258	
KIND CHT	4312	-2303	
MISN SD	4374	-2365	
VIO A	4380	-2371	
SIMP SH	4501	-2492	
SIMP SD	4515	-2506	
ARR	4562	-2553	

8-5/8" 292/2005x, 4 1/2" 4350
DST (1) 4247-92/30-30, GTS/4", GA 2,485
MCFGPD, SPRAY 0/1.3", REC 220'0,
305' GCSW, ISIP 1230#, IFP 1152#
DST (2) 4312-32/30-30-30-30, 320' M
ISIP 1030#, NO FSIP, FP 103-115#
MICT - CO, PF (MISS) 4268-72, SWB
THRU T, VENTING 546 MCFGPD & SWB 1.57
BPPH, 30% 0 THRU 3/4" CK

Check. 4110 -2101 10' sl.
Kind 4338 -2329
Vio. 4394 -2385
LTD&RTD 4603 -2594

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

KANSAS CORPORATION COMMISSION

AUG 13 2009
RECEIVED



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

WHITE & ELLIS DRILLING, INC.
PO BOX 48848
WICHITA, KS 67201-8848

August 18, 2009

Re: WADDLE #1
API 15-185-20718-00-00
26-25S-15W, 3300 FNL 1980 FWL
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after February 14, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888