

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 9090
Name: Charter Energy, Inc.
Address 1: P.O. Box 252
Address 2: _____
City: Great Bend State: Ks Zip: 67530 + 0252
Contact Person: Steve Baize
Phone: (620) 793-9090
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3720 Bottom: 3743 T.D. 3743
LKC Depth to Top: 3386 Bottom: 3552 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - none drilled in 1950
Spot Description: _____
E/2 SW SW Sec. 34 Twp. 21 S. R. 13 East West
660 707 Feet from North South Line of Section
990 4347 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stafford
Lease Name: Gates Well #: 2
Date Well Completed: 1950
The plugging proposal was approved on: 2 / 26 / 2008 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 6 / 29 / 2009
Plugging Completed: 6 / 29 / 2009

KCC
PCT

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		surface	8 5/8	298	none
		production	5 1/2	3720	none

RECEIVED
AUG 04 2009
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the well. Cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 3250'. Mix & pump 15sx gel follow with 50sx cement w/hulls - had good circ. after hole loaded. Pull tubing to 750'. Circ. hole w/90sx cement. Pull tubing. Top off hole w/10sx cement. Tie onto annulus - pressure to 800#. Plugging complete.

Plugging Contractor License #: unknown 99977 KCCPCT Name: Quality Oilwell Cementing
Address 1: PO Box 32 Address 2: _____
City: Russell State: Ks Zip: 67665 + 0032
Phone: (785) 483-2025
Name of Party Responsible for Plugging Fees: Charter Energy, Inc.
State of Kansas County, Barton, ss. _____
Steve Baize (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

AB