

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33094
Name: Cimarex Energy Co.
Address 1: 348 Rd. DD
Address 2: _____
City: Satanta State: KS Zip: 67870 + _____
Contact Person: Melissa Imler
Phone: (620) 276-3693 ext. 14
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: E28234 Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 5188 Bottom: 5192 T.D. 5350
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 055-21879-0000
Spot Description: _____
SW SE SW SE Sec. 34 Twp. 26 S. R. 34 East West
186 193 Feet from North / South Line of Section
1767 1678 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Finney County
Lease Name: Mary Jones Well #: No. 5
Date Well Completed: 08/29/2005
The plugging proposal was approved on: 07/22/2009 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 07/23/2009
Plugging Completed: 07/27/2009

PRT
KCC
PS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Mississippi	Oil & Water	Surface	8 5/8"	1910'	0
Hugoton/Council Grove	Gas & Water	Production	4 1/2"	5350'	2505'
Ogalalla	Water				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

to 5188' 300lbs cottonseed hulls
5188' to 4350' 50 sx common cement
4350' to 1940' mud
1940' to 1790' 50 sx common cement
1790' to 600' mud
600' to 480' 40 sx common cement
480' to 40' mud
40' to surface 10 sx common cement Cement plugs spotted via 2 3/8" tbg

RECEIVED
AUG 03 2009
KCC WICHITA

Plugging Contractor License #: 31151 Name: Sargent and Horton Plugging Inc.
Address 1: Route 1 Box 49BA Address 2: _____
City: Tyrone State: OK Zip: 73951 + _____
Phone: (580) 854-6515
Name of Party Responsible for Plugging Fees: Cimarex Energy Co.
State of Kansas County, Haskell, ss.
Kent Pendergraft Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Kent Pendergraft

PRT