

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Bowman Oil Company
Address: 805 Codell Road Codell, Kansas 67663
Phone: (785) 434-2286 M-F Operator License #: 6931
Type of Well: Oil Well Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: August 3, 2009 (Date)
by: Rich Williams - KCC District #4, Hays, Kansas (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 3448' Bottom: 3691' T.D. 3785'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-23039-0000
Lease Name: Polifka
Well Number: #3
Spot Location (QQQQ): C - SW - SW - NE
2970 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 8 Twp. 13S S. R. 18 East West
County: Ellis County, Kansas
Date Well Completed: June 22, 1982
Plugging Commenced: August 3, 2009
Plugging Completed: August 3, 2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In.	Pulled Out
Lansing	Oil & Water	3448'	3691'	8 5/8"	166'	0'
				5 1/2"	3750'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mix 350 sxs (50 sxs neat-300 sxs Hulls) @ 1782', Mix 135 sxs @ 648', Mix 20 sxs @ 320', Back side held 500 #'s, Top off 5 1/2" with 5 sxs.


Total of 510 sxs of 60/40 Common & Poz Mix with 4% Gel (18 sxs), & 450 #'s Hulls.

See Attached Cement Ticket, ACO-1, Well Log, & Card

KANSAS CORPORATION COMMISSION
AUG 12 2009
KCC PPT
99977 RECEIVED

Name of Plugging Contractor: Quality Oilwell Cementing, Inc. License #: 99977
Address: P.O. Box 32 Russell, Kansas 67665
Name of Party Responsible for Plugging Fees: Bowman Oil Company
State of Kansas County, Rooks, ss.

Connie Jo Austin (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Connie Jo Austin Agent for Bowman Oil Company
(Address) 805 Codell Road Codell, Kansas 67663

SUBSCRIBED and SWORN TO before me this 10th day of August, 2009
Jackie J. Langholz My Commission Expires: 2-24-2013
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PPT

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 3317

Date	8/3/09	Sec.	8	Twp.	13	Range	18	County	Ellis	State	KS	On Location		Finish	2:30 PM			
Lease	Polifka			Well No.	3			Location	Hays, N to Feed lot Rd, 1/2 W, S 1/4									
Contractor	Bowman			Polifka				Owner	To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.									
Type Job	Plug			Hole Size	T.D.			Charge To	Bowman Oil Co.									
Csg.	5 1/2"			Depth				Street										
Tbg. Size	2 3/8"			Depth				City	State									
Drill Pipe				Depth				The above was done to satisfaction and supervision of owner agent or contractor										
Tool				Depth				Cement Left in Csg.	used 510			CEMENT						
Press Max.				Minimum				Amount Ordered	650 ex 60/40 110/10 gal									
Meas Line				Displace				Common	306 @ 10.00			3060.00						
Perf.								Poz. Mix	204 @ 6.00			1224.00						
								Gel.	18 @ 17.00			306.00						
								Calcium										
								Mills	4 # Huls @ 29.00			261.00						
								Salt										
								Flowseal										
EQUIPMENT																		
Pumptrk	9	No.		Cementer	Paul													
Bulktrk	A	No.		Driver	Blake													
Bulktrk	PV	No.		Driver	Doug													
JOB SERVICES & REMARKS																		
Pumptrk Charge	PTA			450.00														
Mileage	7 @ 6.00			42.00														
Footage																		
				60-40 Poz Mix Total			492.00			Handling			679 @ 2.00			1358.00		
Remarks:	Mix 350 ex - 1782'			50 ex - 300' - 450 # Huls						Mileage			8 @ 6.00			550.00		
										Pump Truck Charge			492.00					
FLOAT EQUIPMENT																		
	Mix 135 ex - 648'			450 # Huls						Guide Shoe								
	M.R. 20 ex - 320'									Centralizer								
	Back side weld 500 #									Baskets								
	Top Off 5/2 - 5 ex									AFU Inserts								
QUALITY OILWELL CEMENTING																		
										Rotating Head								
										Squeez Mainfold						307.45		
										Tax						307.45		
										Discount						(1450.00)		
										Total Charge						6108.45		
Signature	Dan Bowman																	

KANSAS CORPORATION COMMISSION
AUG 12 2009
RECEIVED