

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33157
Name: R D Energy, Inc
Address 1: 905 N Montgomery
Address 2: _____
City: Sedan State: KS Zip: 67361 + _____
Contact Person: Rod Dickens
Phone: (620) 725-3065
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Peru-Sedan Depth to Top: 1000 Bottom: 1050 T.D. 1200

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 019-19255 - 0000
Spot Description: _____
nw - ne - ne - ne Sec. 33 Twp. 33 S. R. 11 East West
5,100 Feet from North / South Line of Section
570 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Chautauqua
Lease Name: Griffith Well #: 5
Date Well Completed: _____
The plugging proposal was approved on: 4/24/09 (Date)
by: D. Simms (Elmore) (KCC District Agent's Name)
Plugging Commenced: 4/24/09
Plugging Completed: 4/24/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Peru-Sedan	Oil	Production	5 3/16"		none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 1" to 1180'. Spotted 10 sacks cement inside 5 3/16" casing. Pulled 1". Perforated casing at 750' and 350'. Ran 1" to 750 and spotted 8 sacks cement. Pulled 1" to 350'. Cemented to surface inside and outside of casing with 114 sacks cement.

KANSAS CORPORATION COMMISSION

**AUG 07 2009
RECEIVED**

Plugging Contractor License #: 32884 Name: Elmore's Inc
Address 1: 776 Hwy 99 Address 2: _____
City: Sedan State: KS Zip: 67361 + _____
Phone: (620) 249-2519
Name of Party Responsible for Plugging Fees: R D Energy, Inc
State of Kansas County, Chautauqua, ss.
Ron L Mercer Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Ron Mercer

RKT

STATEMENT

8222

ELMORE'S INC.

Box 87 - 776 HWY99
Sedan, KS 67361
Cell: (620) 249-2519
Eve: (620) 725-5538

Date
4-24-09

Customer R D Energy (Mercer) Nor Tex
Address _____
City Duane Sims State _____ Zip _____
GRIFFITH No. 5

Qty.	Description	Price	Amount
132	SKS Cement	7.95	1049.40
3	SKS Gel	15.00	45.00
1180'	1" Tubing	.10	118.00
3	hr Water Truck	80.00	240.00
3	hr Cement Pump	100.00	300.00
1	Bank Tank	80.00	80.00
3	hr Pulling Unit	95.00	285.00
2	Perforations 750 + 350	100.00	200.00
1	hr Back hoe	50.00	50.00
			2367.40
	Ran 1" To 1180' Gel	Tax	149.15
	Hole Spotted 10 SKS	\$	2516.55
	Cement Inside 5 3/16		
	Casing Pulled 1" out Perforated		
	Casing At 750' + 350' Ran 1" In 4" 750'		
	Spotted 8 SKS Cement Pulled Up to 350'		
	Cemented To Surface Inside + Out With		

Thank You - We appreciate your business! 114 SKS Cement

Rec'd. by _____

TERMS: Account due upon receipt of services. A 1 1/2% Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.

KANSAS CORPORATION COMMISSION

AUG 07 2009

RECEIVED