

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

KANSAS CORPORATION COMMISSION

AUG 06 2009

RECEIVED

*Amended*

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Daystar Petroleum  
Address: P.O. Box 360 Valley Center, Ks 67147  
Phone: (316) 755-3492 Operator License #: 30931  
Type of Well: Oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Virgil Clothier (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

API Number: 15-154-01747-0000  
Lease Name: Sam Ainsworth  
Well Number: 6  
Spot Location (QQQQ): \_\_\_\_\_ - SW - NE - NW  
9904302 Feet from 4 North /  South Section Line  
16503778 Feet from  East / ~~West~~ Section Line  
Sec. 30 Twp. 18 S. R. 7  East  West  
County: Rice  
Date Well Completed: \_\_\_\_\_  
Plugging Commenced: 7-07-09  
Plugging Completed: 7-08-09

*KCC PER PERGOS*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4"	203'	none
				6"	3180'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf. Well at 1050', 700', and 260'. Ran 2 7/8" tubing to 3100', mixed 100 sacks of 06/40 pos 4% gel with 150# hulls. Pulled tubing to 1050', mixed 50 sacks cement. Pulled tubing to 700', mixed 50 sacks cement. Pulled tubing to 260', mixed 40 sacks cement and circulated to surface shut in 6" casing, mixed 25 sacks cement. Didn't come around. Pulled tubing, hooked on annulus, mixed 6 sacks cement. Pressured up to 300#. Topped of with 20 sacks cement. Plugging Complete

Name of Plugging Contractor: Mike's Testing and Salvage Inc. License #: 31529  
Address: P.O. box 467 Chase, Ks. 67524

Name of Party Responsible for Plugging Fees: Daystar Petroleum  
State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Mike Kelso*  
(Address) P.O. box 467 Chase, Ks. 67524

SUBSCRIBED and SWORN TO before me this 27 day of July, 2009

*Irene Herzberg*  
Notary Public

My Commission Expires:

