

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Trans Pacific Oil Corporation
Address: 100 S. Main, Suite 200, Wichita, KS 67202
Phone: (316) 262-3596 Operator License #: 9408
Type of Well: Injection Docket #: E-15,539
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 8/6/09 (Date)
by: Pat Bedore (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-167-20389-0000
Lease Name: Sebesta
Well Number: #9
Spot Location (QQQQ): E2 - NE - SW -
2280 Feet from North / South Section Line
2970' Feet from East / West Section Line
Sec. 24 Twp. 14S S. R. 11 East West
County: Russell
Date Well Completed: 1970
Plugging Commenced: 8/6/09
Plugging Completed: 8/6/09

KCC PAT
PAT
GPS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	289'	
				4-1/2"	2912'	

KANSAS CORPORATION COMMISSION
AUG 11 2009
RECEIVED

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Klima well service MIRU to plug. Perf Tech perforated 2 holes each @ 1200', 507', 275' tkt. # 6602, Ran in 2 7/8" tbg to 2800'.
Quality Cementing tkt. # 3414. Spot 100 sx 60/40 poz mix 4% gel with 300#s hulls, pulled to 1300,
spot 60 sx and 200 hulls circ. up 4 1/2' casing, shut 4 1/2 valve circ up 8 5/8 with 70 sx. pulled remaining tbg,
tied onto 4 1/2 mix 30 sx pressured to 200#s shut in with 100#s. Used 260 sx and 500 # Hulls. KCC Rep. Pat Bedore.

Name of Plugging Contractor: Klima Well Service, Inc. License #: 7023
Address: P.O. Box 386, Claflin, KS 67525-0386


Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation
State of Sedgwick County, Kansas, ss.

Gary Sharp (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gary Sharp
(Address) 100 S. Main, Suite 200, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 10th day of August, 20 09

Glenna E. Lowe My Commission Expires: _____
Notary Public



PAT