

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Oxy USA, Inc  
Address: PO Box 2528 Liberal KS 67905  
Phone: 620.629 4200 Operator License #: 5447  
Type of Well: D+A Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 7-20-09 (Date)  
by: Jerry Stapleton (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Morrow Depth to Top: 4877 Bottom: 4881 T.D. 5214  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-129-21238<sup>6</sup>-0000  
Lease Name: Hanke Trust  
Well Number: 1  
Spot Location (QQQQ): \_\_\_\_\_ - NE-SW  
1980 Feet from  North /  South Section Line  
1980 Feet from  East /  West Section Line  
Sec. 8 Twp. 33 S. R. 42  East  West  
County: Morton  
Date Well Completed: 10-18-93 spud  
Plugging Commenced: 7-21-09  
Plugging Completed: 7-21-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1301	—
				5 1/2	5199	1935

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP+ 2 sx 4810 to 4794 (Already set). Loaded 5 1/2 w/mud. Shot & pulled to 1330. Circ. hole w/mud & mixed 50 sx plug 1330 to 1180 40 sx 400 to 280 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151  
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731  
Name of Party Responsible for Plugging Fees: Oxy USA Inc, 1701 N. Kansas, PO Box 2528, Liberal, KS. 67905

State of Kansas County Seward, ss.  
Kenny Andrew Kenny (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is true and correct, and the same are true and correct, so help me God.

RECEIVED

AUG 10 2009

KCC WICHITA

ANITA PETERSON  
Notary Public - State of Kansas  
My Appt. Expires October 1, 2009

(Signature) Kenny Andrew Kenny  
(Address) \_\_\_\_\_  
SUBSCRIBED and SWORN TO before me this 6<sup>th</sup> day of Aug, 2009  
Anita Peterson My Commission Expires: Oct. 1, 2009  
Notary Public

*[Handwritten initials]*