

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: SWD Docket #: D-3010
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7/3/09 (Date)
by: Rich Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3499 Bottom: 3923 T.D. 3923
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-05898-0001
Lease Name: Hall B
Well Number: #3
Spot Location (QQQQ): _____ - NW - SW - NW
1654.6 Feet from North South Section Line
330 Feet from East West Section Line
Sec. 26 Twp. 11S S. R. 17W East West
County: Ellis
Date Well Completed: 1/6/38
Plugging Commenced: 7/7/09
Plugging Completed: 7/7/09

KCC DISTRICT AGENT
CP 2/13

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10.75	1109	380 sx
				7	3383	250 sx
				5-1/2	3327-3499	50 sx

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Dug out WH - had to jack hammer cement to be able to orange peel surface casing. 15.5" full of cement. Perf'd at 1160'. Ran tbg to 2515'.
Spotted 14 sx gel above 15 sx cement. Pulled tbg to 1616' and circ 210 sx 60/40 poz w/4% gel w/200# hulls to surface. TOH w/tbg.
Topped off 7" w/40 sx w/50# hulls. Connected to 10 3/4" and pressured to 500# - held. Connected back to 7" and pumped
160 sx cement w/150# hulls. SIP - 200#. Approved by Rich Williams w/KCC.


Name of Plugging Contractor: Smoky Hills Well Service License #: 5022 32452
Allied Cementing Co., Inc.
Address: P.O. Box 31, Russell, KS 67665-0031

Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss. _____
at Canaday (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 1700 Waterfront Parkway, Bldg. 500, Wichita KS 67206

SUBSCRIBED and SWORN TO before me this 5th day of August 2009
[Signature] My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC DISTRICT AGENT
CP 2/13

RECEIVED
AUG 10 2009

KCC WICHITA

[Handwritten initials]

WELL RECORD

Company Cities Service Oil Co. Well No. 3 Farm Hall "B" S. W. D.
 Location 1654.6' South and 330' East of NW Cor. Sec. 26 T. 11 R. 17W
 Elevation 1927 County Ellis State Kansas
 Drlg. Comm. January 20, 1952 Contractor Holm Drilling Company
 Drlg. Comp. February 15, 1952 Acid _____
 T. D. 3923' Initial Prod. Input Test: Ind. Capacity 3438 bbls. water per hr.
(2-15-52)

DEEPENING FOR SALT WATER DISPOSAL

CASING RECORD:

7" @ 3383' cem. 250 ex cement
 172' of 5-1/2" liner at 3499' with 50 sacks cement.

Top Arbuckle	3382'
Top Reagan	3681'
Top Granite	3923'
Total Depth	3923'

FORMATION RECORD:

Old T. D. 3499'
 Cement squeezed old perforations at 3421-28.
 lime & iron 3499-3501'
 lime 3722
 sand 3727
 lime 3881
 sand 3922½
 granite 3923 T. D.

3923
 3381

RECEIVED
 AUG 10 2009
 KCC WICHITA

ALLIED CEMENTING CO., LLC. 34923

P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Russell

DATE <u>7-7-09</u>	SEC <u>26</u>	TWP. <u>11</u>	RANGE <u>17</u>	CALLED OUT	ON LOCATION	JOB START <u>1:00pm</u>	JOB FINISH <u>2:00pm</u>
LEASE <u>4411</u>	WELL # <u>B # 3</u>	LOCATION <u>Codel River Rd 5ct</u>	COUNTY <u>Ellis</u>		STATE <u>Ks.</u>		
<input checked="" type="radio"/> OLD OR NEW (Circle one)			<u>2 1/4 S Winta</u>				

CONTRACTOR Smoky Hill well Service OWNER _____

TYPE OF JOB PTA

HOLE SIZE 9 5/8" T.D. _____

CASING SIZE 7" DEPTH _____

TUBING SIZE 2 7/8" DEPTH 2516'

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

CEMENT

AMOUNT ORDERED 425 1/4 49.6-1

14 Gel 300# hulls

COMMON	<u>255</u>	@	<u>13.54</u>	<u>3442.50</u>
POZMIX	<u>170</u>	@	<u>7.55</u>	<u>1283.50</u>
GEL	<u>28</u>	@	<u>20.25</u>	<u>567.00</u>
CHLORIDE		@		
ASC		@		
<u>Hulls</u>	<u>3</u>	@	<u>31.05</u>	<u>93.15</u>
		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	225	@	<u>2.25</u>	<u>506.25</u>
MILEAGE				<u>450.00</u>
TOTAL				<u>6342.40</u>

EQUIPMENT

PUMP TRUCK CEMENTER Shane

417 HELPER Matt

BULK TRUCK

481 DRIVER Chris

BULK TRUCK

_____ DRIVER _____

REMARKS:

2516' 14 Gel tail 15 sks Cement
Pulled up to 1600' to Circulate Cement
~~15 sks Cement~~
Took 200 sks with 200# hulls
Came out of Hole put swage on
Mixed 200 sks + shot in @ 200 psi
Pressured up 10 3/4 to 500 psi
Mixed 150 #hulls down 5'


SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>875.00</u>
EXTRA FOOTAGE	@		
MILEAGE	<u>20</u>	@	<u>207.00</u>
MANIFOLD	@		
	@		
	@		

CHARGE TO: Vess Oil

STREET _____

CITY _____ STATE _____ ZIP _____



TOTAL 11015.00

RECEIVED

AUG 10 2009

PLUG & FLOAT EQUIPMENT

KCC WICHITA

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME _____

SIGNATURE [Signature]

SALES TAX (If Any) _____

TOTAL CHARGES [Signature]

DISCOUNT [Signature] IF PAID IN 30 DAYS