

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Scheck Oil Operation
Address: 211 S Front Russell, KS. 67665
Phone: (316) 755-3523 Operator License #: 9292
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Virgal Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-01960-00-00
Lease Name: R J Warner A
Well Number: 6
Spot Location (QQQQ): NE NW - N/2 - N/2 - NW
3204944 Feet from North / South Section Line
13203973 Feet from East / West Section Line
Sec. 36 Twp. 18 S. R. 8 East West
County: Rice
Date Well Completed: _____
Plugging Commenced: 7-16-09
Plugging Completed: 7-21-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10"	382'	none
				7"	3187'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf well at 1100', 750', 420', and 250'. Ran 2 7/8 tubing 3200', mixed 50 sacks of cement with 200# hulls. Displaced to 3200'. Pulled up to 1100' mixed 50 sacks, no circulation. Pulled up to 750', pumped 40 barrels of water. Checked hole, no plug at 1100' mixed 50 sacks cement 3%cc. Tagged cement at 1100', pulled up to 750', mixed 50 sacks cement. Tagged cement at 700', pulled up to 420', mixed 50 sacks cement. Tagged cement at 300', pulled up to 250' and mixed 60 sacks cement and circulated to surface. Tied onto annulus and mixed 80 sacks cement. Topped off with 75 sacks of cement. Plugging Complete.

Name of Plugging Contractor: Mike Testing and Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, KS. 67524

Name of Party Responsible for Plugging Fees: Scheck Oil Operation
State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso
(Address) P.O. Box 467 Chase, KS. 67524

SUBSCRIBED and SWORN TO before me this 6 day of August, 2009

Irene Herzberg
Notary Public

My Commission Expires: _____
NOTARY PUBLIC - State of Kansas
IRÈNE HERZBERG
My Appt. Exp. 8-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

159,
KCC Pkt
per
GPS

AUG 10 2009
RECEIVED

[Handwritten initials]