

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD #4
K.A.R.-82-3-117

15-163-19414-0000

API NUMBER Spud 2-18-63

LEASE NAME Vohs

WELL NUMBER 9

990 Ft. from N Section Line

990 Ft. from E Section Line

SEC. 12 TWP. 10 RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 3-2-63

Plugging Commenced 4-17-93

Plugging Completed 4-28-93

RECEIVED
STATE CORPORATION COMMISSION
5-12-93
MAY 12 1993

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Conservation Division
Wichita, Kansas & Gas Corporation

ADDRESS 155 N. Market, Suite 350, Wichita, KS 67202

PHONE# (316) 267-8011 OPERATORS LICENSE NO. 5652

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Lansing/KC Depth to Top 3391' Bottom T.D. 3795'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	202'	None
				5-1/2"	3792'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
SEE BACK

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bill's Well Service License No. Unknown

Address Codell, KS 67630

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mustang Oil & Gas Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Stan Brady, Vice President

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stan Brady

(Address) As Above



AND SWORN TO before me this 10th day of May, 1993


Patricia A. Reilly
Notary Public

My Commission Expires: August 11, 1995

TIH w/tbg. Tbg set @1,623'. Cmt'd w/100 sxs common w/0.25#/sx Flocele & 165 sxs 60/40 pozmix, 8% gel, 0.25#/sx Flocele & 300# hulls. Cmt did circulate. TOOH w/tbg. Pumped additional 20 sxs, 60/40 pozmix. Pressured to 300 psi. Pump 15 sxs down surface pipe annulus. Pressured to 1000 psi. SI. Completed plugging operations @11:15 a.m., 4-28-93. State plugger was Dennis Hamel.

NO. 2
APR 29 1993
STATE OF KANSAS

PATRICIA A. KELLEY
NOTARY PUBLIC
STATE OF KANSAS
MY COMM. EXPIRES APR 29 1993



SINCLAIR OIL & GAS COMPANY - Operator SIERRA PETROLEUM CO., INC - Contractor

H. J. VOHS #9
SW NE NE
Sec. 12-10S-19W
Rooks County, Kansas

T. D.: 3795'

Commenced: 2-18-63
Completed: 3-2-63

Casing:	Cement:
10-3/4" Set at 202' G.I.	with 150 sx. Howco
5-1/2" Set at 3792'	with 300 sx. Howco

FORMATION	DEPTH
Sand & Shale	210
Shale & Shells	995
Shale, Sand & Shells	1240
Red Bed	1595
Anhydrite	1632
Shale & Shells	1890
Shale & Lime	3220
Lime	3530
Lime & Chert	3580
Lime	3670
Cherty Lime & Shale	3740
Lime	3770
Arbuckle	3795

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is correct and true to the best of my knowledge.

O.T. Honaker
Drilling Superintendent

Subscribed and sworn to before me this 5th day of March, 1963.

Leroy Ditz
Notary Public

My commission expires: 10-17-63

RECEIVED
STATE CORPORATION COMMISSION

MAY 12 1993

CONSERVATION DIVISION
Wichita, Kansas