

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-00259-0000

API NUMBER _____

LEASE NAME Vohs

WELL NUMBER #1

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 14 TWP. 10S RGE. 19W (EXR) (W)

COUNTY Rooks

Date Well Completed 6-25-45

Plugging Commenced 8-27-90

Plugging Completed 8-27-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mustang Companies, Inc.

ADDRESS P.O. Box 1609, Great Bend, Kansas 67530

PHONE#(316 792-7323 OPERATORS LICENSE NO. 5652

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-27-90 (date)

by Marion Schmidt (KCC District Agent's Name).

Is AC0-1 filed? _____ If not, is well log attached? yes

Producing Formation Arbuckle, Lansing Depth to Top _____ Bottom _____ T.D. _____

_____ KC
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	oil	3549	3562	5 1/2"	3549'	-0-
LKC	oil	3262	3472			
Toronto	oil	3242	3450			Set CIBP @ 3100'
Topeka	oil	3167	3173			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Run 2 7/8" tubing to 3050'. Spot 150 sxs cement w/ 4 1/2" sxs hulls. Perforate 5 1/2" w/ 3 holes @ 1420'. Pull tubing to 1170'. Pump 90 sxs cement thru tubing and circulate to surface. Pull out of hole w/ tubing. Pumped 100 sxs down 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing/Express Well Service License No. _____

Address P.O. Box 31, Russell, KS 67655 P.O. 426, Victoria, Kansas 67672 9-28-90


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mustang Companies, Inc. 9-28-90

STATE OF Kansas COUNTY OF Barton, ss.

J.P. Meroney (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J.P. Meroney
J.P. Meroney, Senior Vice President
(Address) P.O. Box 1609, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 25th day of September, 19 90



Pamela K. Walters
Notary Public
Pamela K. Walters
Commission Expires: August 25, 1991