

STATE CORPORATION COMMISSION  
2000 Grand Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R. -82-3-117

15-163-0370S-0000  
API NUMBER compl 2-18-46

LEASE NAME Vohs

WELL NUMBER 3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

3630 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR Mustang Oil & Gas Corporation

SEC. 14 TWP. 10S RGE. 19 (E) or (W)

ADDRESS 155 N. Market, #350, Wichita, Kansas

COUNTY Rooks

PHONE# (316) 267-8011 OPERATORS LICENSE NO. 5652

Date Well Completed 2-18-46

Character of Well Oil

Plugging Commenced 7-27-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-27-92

The plugging proposal was approved on 7-27-92 (date)

by Dennis Hammel - KCC's representative (KCC District Agent's Name).

Is ACO-1 filled? yes If not, is well log attached? \_\_\_\_\_

Producing Formation L-KC Depth to Top 3265 Bottom 3510 T.D. 3612

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Anhydrite	Shale & Lime	1432	1440	8-5/8	1440	None
L-KC	Shale & Lime	3265	3510	5-1/2	3510	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TIH w/tbg to 3155'. Spot 120 sxs cmt to 1410'. Pull tbg up to 1410'. Perf @ 1450'. Fill w/cmt inside and outside to surf. Sq prod csg & prod/csg annulus to 500 psi. SI @ 300 psi. Total 325 sxs of 60/40 poz w/10% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mustang Oil & Gas Corporation License No. 5652

Address P.O. Box 1609, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mustang Oil & Gas Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Stan Brady, Vice President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Stan Brady

(Address) 155 N. Market, #350  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 10th day of August, 19 92

Kandy Hanson RECEIVED  
Notary STATE CORPORATION COMMISSION  
Kandy Hanson 8-11-92

My Commission Expires: 11-6-94



AUG 11 1992  
Form CP-4  
Revised 05-88  
CONSERVATION DIVISION  
Wichita, Kansas