

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-20686-00-00  
Spot: SENE SW Sec/Twnshp/Rge: 11-19S-15W  
1650 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: PASCOE D Well #: 1  
County: BARTON Total Vertical Depth: 3580 feet

Operator License No.: 5617  
Op Name: THE PYRAMID CORPORATION, INC.  
Address: 1030 VINCENT ST  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	923	0	450 SX
PROD	5.5	3600	1766	50 SX

116.35

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/13/2009 9:00 AM  
Plug Co. License No.: 31528 Plug Co. Name: KELSO, MIKE OIL, INC.  
Proposal Rcvd. from: MIKE KELSO Company: THE PYRAMID CORPORATION, IN Phone: (620) 938-2943

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/13/2009 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off bottom and topped with 5 sxs cement.  
Cut casing 1766' - pulled to 1500' - tied to casing and pumped 150 sxs cement with 200# hulls.  
Pulled casing to 900' - pumped 40 sxs cement with 150# hulls.  
Pulled casing to 300' - pumped 120 sxs cement with 100# hulls - circulated cement to surface.  
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3600	3610		

INVOICED

DATE 9/9/09  
INV. NO. 2010060225

RECEIVED  
JUL 20 2009  
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING-TEICKET #C33028.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

Form CP-2/3

PKT

JUL 15 2009

THE PYRAMID CORPORATION, INC. #1 PASCOE "D" 11-19-15W  
 SUITE 110 3000 W. KELLOGG, WICHITA, KS. SE NE SW  
 CONTR RED TIGER DRILLING CTY BARTON

GEOL CARL TODD FIELD OTIS-ALBERT

E 1962 KB CM6/26/72 <sup>CARD</sup>ISSUED 11/16/72 IP EST. 25 BOPD + WTR  
 REAGAN SD 3600-10

+	+	+
+	+	+
+	+	+

API 15-009-20,686

SMP	TOPS	DEPTH	DATUM
SC		905	+1057
TOP		2930	-968
HEEB		3179	-1217
TOR		3194	-1232
DOUG		3208	-1246
BN LM		3257	-1295
LANS		3267	-1305
BKC		3491	-1529
CONG		3530	-1568
ARB		3580	-1618
REAGAN		3582	-1621
TD		3610	-1548

8 5/8" 923/450SX; 5 1/2" 3600/50SX  
 DST(1) 3315-30(LANS)/30-30-30-30, 80'  
 MW, BHP 907-870#, FP 40-68#  
 DST(2) 3432-80(LANS)/30-30-30-30, 3'M,  
 ALL PRESS 37#  
 DST(3) 3583-90(REAGAN)/45-15-30-15, 65'  
 OSP THIN M, BHP 123-95#, FP 37-95#  
 DST(4) 3590-3600(REAGAN)/45-45-45-45,  
 30'HO&GC THIN M, 50'OC THIN M, BHP  
 861-861#, FP 27-49#  
 DST(5) 3600-10(REAGAN)/45-45-45-45, GTS  
 /41" TSTM, 210'SL MCO, 70'OCW, 120'  
 WTR, BHP 923-891#, FP 43-184#  
 MICT, CO TO 3610 TD, FU 250'OIL, 400'W  
 FROM 4000 GAL OIL X 36,000#SD, SWB PT  
 LD & POP.  
 NO LOG

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

3010090392  
 11/18/72

110-32