

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-20846-00-02
Spot: SESESESE Sec/Twnshp/Rge: 35-23S-21E
60 feet from S Section Line, 100 feet from E Section Line
Lease Name: C STEWART Well #: 5-80
County: BOURBON Total Vertical Depth: 714 feet

Operator License No.: 3728
Op Name: KENT, ROGER DBA R J ENTERPRISES
Address: 22082 NE NEOSHO RD
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6	20		
PROD	2	714		

35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/02/2009 3:00 PM
Plug Co. License No.: 3728 Plug Co. Name: KENT, ROGER DBA R J ENTERPRISES
Proposal Rcvd. from: JASON KENT Company: RJ ENTERPRISES Phone: (785) 448-6995

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO 714' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 07/02/2009 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:
1" PIPE WAS RAN INTO THE CASING TO TD. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:
INVOICED
DATE 9/9/09
INV. NO. 2010060226

RECEIVED
KCC DISTRICT #3
JUL 16 2009 *Sh*
CHANUTE, KS

RECEIVED
JUL 20 2009
KCC WICHITA

Remarks: GPS LOCATION 37.99423 N & 095.06056 W.

Plugged through: TBG

District: 03

Signed Clayton P. Titel by Sh
(TECHNICIAN)

PKT