

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22984-00-00
Spot: SEWNWE Sec/Twnshp/Rge: 19-16S-14W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: OCHS Well #: 1
County: BARTON Total Vertical Depth: 3432 feet

Operator License No.: 33530
Op Name: REIF OIL & GAS COMPANY LLC
Address: PO BOX 298
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	402	0	w/235 sxs cmt
PROD	4.5	3430	0	w/200 sxs cmt

111.54

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2009 9:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: DON REIF Company: REIF OIL & GAS COMPANY LLC Phone: (620) 786-5698

Proposed Plugging Method: Ordered 500 sxs 60/40 pozmix - 4% gel - 500# hulls.
Emergency plug with rig over the hole.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/15/2009 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3396' - tied to tubing and pumped 125 sxs cement with 200# hulls.
Pulled to 2000' - pumped 100 sxs cement with 200# hulls.
Pulled to 800' - pumped 50 sxs cement with 100# hulls - circulated cement to surface.
Pulled tubing - tied onto casing - pressured to 400# P.S.I. with 10 sxs.

Perfs:

RECEIVED
JUL 20 2009
KCC WICHITA

INVOICED
DATE 9/9/09
INV. NO. 2010060227

Remarks: QUALITY OILWELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

JUL 17 2009

5/11

7660906106
201P1P

RECEIVED

1125

BOGER BROTHERS OIL INC.

102 N. WALNUT
HOISINGTON, KS 67544

#1 OCHS


19-16-14W
SE NW NE

CONTR ALLEN DRLG. CO.

CTY BARTON

GEOL DICK FOLEY

FIELD HERMAN EXT (1/4 S)



ELV 1930 KB SPD 12/17/82 CARD ISSUED 2/10/83 IP P 36 BOPD, NW
1925 GL
API 15-009-22,984 ARB OH 3430-3432
(NEW PAY)

SMP	Tops	Depth/Datum	
ANH	933+ 997	8 5/8 " 402/235SX; 4 1/2 " 3430/200SX
TOP	2867- 937	DST (1) 3122-90 (LANS) / 30-30-60-30, 608' GIP, REC 1140' SW, NS, SIP 624-583#, FP 219-281 / 365-469#
HEEB	3096-1166	DST (2) 3192-3213 (LANS) / 30-30-30-30, 600' GIP, REC 30' DARK GREY HOGCM, 60' BLACK MDY GSY O, SHOW FO IN BTM OF TST, SIP 697-656#, FP 63-52 / 73-63#
TOR	3115-1185	DST (3) 3217-50 (LANS) / 30-30-60-30, REC 300' SW, SIP 690-697#, FP 83-94 / 146-177#
LANS	3159-1229	DST (4) 3324-60 (LANS) / 30-30-60-30, REC 50' THIN M, NS, SIP 853-603#, FP 83-83 / 94-94#
BKC	3396-1466	DST (5) 3394-3420 (ARB) / 30-30-15-15, REC 10' M, NS, SIP 52-41#, FP 31/31#
CONG	3400-1470	DST (6) 3393-3432 (ARB) / 30-30-30-30, 60' GIP, REC 130' OCM, 180' HOGCM, W/TR WTR, SIP 977-946#, FP 146-135 / 177-187#
REW ARB	3418-1488	MICT - CO, (ARB OH 3430-32), AC 200G (15% NE), SWB LD, GSO, POP, P 36 BOPD, NW, 1/19/83
ARB	3427-1497	
RTD	3432-1502	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS