

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20581-00-02
Spot: N2SESE Sec/Twnshp/Rge: 11-17S-31W
1100 feet from S Section Line, 660 feet from E Section Line
Lease Name: PEMBER 11D Well #: 1
County: SCOTT Total Vertical Depth: 4630 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	316		WITH 180 SX CMT
PC		2251		WITH 335 SX CMT TO SURFACE
PROD	5.5	4620	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2009 2:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 216-0330

Proposed Plugging Method: PUMP 40 SX CMT & 150# HULLS-GEL SPACER TO ANHYDRITE. CMT TO SURFACE. CHECK BACKSIDE.

150.48

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2009 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG PUMP 40 SX CMT -150# HULLS -35 BBL GEL WATER SPACER TO 2300'.
PUMP 275 SX CMT FROM 2300' TO 0'. PRESSURE TO 550# & HELD. 2ND PLUG PUMP
10 SX CMT DOWN ANNULUS. PRESSURE TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4366	4370		
4301	4304		
4176	4180		
4037	4044		

INVOICED

DATE 9/9/09
INV. NO. 2010060228

KANSAS CORPORATION COMMISSION

JUL 31 2009

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

[Signature]

(TECHNICIAN)

RECEIVED

JUL 20 2009

KCC DODGE CITY

Form CP-2/3