

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21569-00-00
Spot: NENESW Sec/Twnshp/Rge: 14-9S-24W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: NICKELSON Well #: 1
County: GRAHAM Total Vertical Depth: 4031 feet

Operator License No.: 6861
Op Name: RON'S OIL OPERATIONS INC
Address: 1889 200TH AVE
PENOKEE, KS 67659

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	215	0	w/unknown sxs cmt
PROD	4.5	4030	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/22/2009 8:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: TERRY GARRISON Company: RON'S OIL OPERATIONS INC. Phone: (785) 216-0588

Proposed Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Well was DV'd.
Method: Operator elected all cement plug.

131.01

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/22/2009 10:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Washed down well to 4000'. Sand broke in - shot tubing off at 3595'.
Poe Service RIH with tubing to 3500'.
Allied rigged to tubing and pumped 75 sxs cement with 200# hulls.
Pulled tubing to 2650' - pumped 75 sxs cement with 200# hulls.
Pulled tubing to 1250'. Allied rigged to tubing and pumped 45 sxs cement to circulate cement to pit - 100# hulls were mixed in.
Pulled tubing - rigged to 4 1/2" casing with a swedge and pumped 20 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Rigged to 8 5/8" - cement blew out of well head instantly.

Perfs:

Top	Bot	Thru	Comments
3932	3936		
3875	3879		

INVOICED
DATE 9/9/09
INV. NO. 2010060229

KANSAS CORPORATION COMMISSION

JUL 27 2009

RECEIVED

Remarks: ALLIED CEMENTING COMPANY-TICKET #037584.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

Form CP-2/

JUL 23 2009

10/1

255000100
20/10/10


replacement card

MAVERICK PETROLEUM
HAYS KS 67601

1 NICKELSON

14-09S-24W
NE NE SW

site: 5-1/4 S OF PENOKEE, KS city: GRAHAM API 15-065-21569
 contr: PIONEER DRILLING field: HOLLEY SE.
 geol:
 fr spd drig card last
 date 01/21/82 date 01/25/82 comp 01/31/82 issued 09/30/82 revised 09/15/97



ELV: 2480 TOPO
 tops.....depth/datum
 RTD.....4031.-1551.
 NO TOPS RPTD

IP status:
 OIL, LKC, INTV NA, 09/23/82
 INFO RELEASED: 9/15/97 -- WAS OIL WELL -- TEMP
 COMP
 CSG: 8-5/8" 215, 4-1/2" 4030
 NO CORES
 DSTS TAKEN - DETAILS NA
 MICT - CO, PF (LKC) INTV NA, AC'D, SO, POP, OIL
 WELL (POTENTIAL NOT RPTD), 9/23/82 - NO OTHER
 INFO RELEASED BY OPERATOR OR ON KCC
 RECORDS; ALL REQUESTS FOR INFO DENIED

COPYRIGHT 1997
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS