

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05076-00-01
Spot: SENENW Sec/Twnshp/Rge: 16-11S-18W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: WASINGER Well #: 1
County: ELLIS Total Vertical Depth: 3533 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	13.38	155	0	200 SX
PROD	5.5	3531	0	750 SX

114.82

Well Type: EOR UIC Docket No: E18064.1 Date/Time to Plug: 07/24/2009 11:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 700# hulls - 12 sxs gel.
Tubing and junk in the hole at 3100'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/24/2009 2:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Klima Well Service RIH with tubing to 2835'.
Quality Oilwell rigged to tubing and pumped 10 sxs gel followed with 100 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in.
Pulled tubing to 1300'. Quality Oilwell rigged to tubing and pumped 130 sxs cement with 200# hulls to circulate cement to pit.
Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 15 sxs cement to fill casing to surface.
Rigged to 8 5/8" casing and pumped 10 sxs cement.
Max. P.S.I. 250#. S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3364	3369		
3318	3322		
3311	3315		
3301	3306		
3179	3184		
3151	3153		
3146	3147		
3123	3124		


RECEIVED
AUG 04 2009
KCC WICHITA

INVOICED
DATE 9/9/09
INV. NO. 2010060233

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #3352.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

CM

PAT

10/16

ES0000105
P.O.P.P

SHADE & BERRY

#1 WASINGER

D
∞
16-11-18W
SE NE NW

Contr. TRANSIT CORP

ELLIS County

E 1900RB Comm.

Comp. 5-8-58


IP

10 BOPD

Tops	Depth	Datum
TOP	2880	-980
HEEB	3100	-1200
TOR	3120	-1220
LANS	3145	-1245
B/KC	3370	-1470
CONG	3400	-1500
SIMP	3458	-1558
ARB	3484	-1584
TD	3533	-1633

Casing
 5" 3531-750 SKS ^{13 3/4} - 155 w/200 SKS
 PERF 3311-22: ACID 250: 1 BOPH
 & 50% WTR: PERF 3364-69: ACID
 500: SQZ: PERF 3310-15: TST WTR:
 SQZ: PERF 3179-84: ACID 1000:
 SWB 70. BOPH

NEDDAM POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS