

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-29908-00-00  
Spot: SESESENW Sec/Twnshp/Rge: 6-24S-19E  
2805 feet from S Section Line, 2805 feet from E Section Line  
Lease Name: L THOMPSON Well #: 1A  
County: ALLEN Total Vertical Depth: 1002 feet

Operator License No.: 32073  
Op Name: THOMPSON, JEROME A. DBA THOMPS  
Address: 2260 N DAKOTA RD  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20	0	

35.00

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/21/2009 10:00 AM

Plug Co. License No.: 33977 Plug Co. Name: E K ENERGY LLC

Proposal Rcvd. from: DAVE KIMSEY Company: E.K.ENERGY Phone: (620) 496-6257

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 1002'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 500', AND TO PLACE A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/21/2009 1:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

DRILL PIPE WAS RAN INTO THE WELL TO TD. A 50' CEMENT PLUG WAS PUMPED THROUGH THE DRILL PIPE TO T.D.. THE DRILL PIPE WAS PULLED TO 500' AND A 50' CEMENT PLUG WAS PUMPED TO THAT DEPTH. THE PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE DRILL PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED  
KCC DISTRICT #3

JUL 22 2009 CPT

CHANUTE, KS

INVOICED  
DATE 9/9/09  
INV. NO. 2010060234

KANSAS CORPORATION COMMISSION

JUL 27 2009  
RECEIVED

Remarks:

Plugged through:

District: 03

Signed

*Clayton P. Titel*

(TECHNICIAN)

PKT