

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22166-00-01
Spot: E2NWSW Sec/Twnshp/Rge: 7-11S-18W
2020 feet from S Section Line, 4291 feet from E Section Line
Lease Name: CAVE Well #: 12
County: ELLIS Total Vertical Depth: 3625 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1318	0	500 SX
PROD	5.5	3624	0	200 SX

117.81

Well Type: EOR UIC Docket No: E23474.5 Date/Time to Plug: 07/22/2009 11:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 700# hulls - 12 sxs gel.
Junk in the hole at 2800'.
Shoot perf at 1250'.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/22/2009 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2823' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 2623' - pumped 12 sxs gel - then 20 sxs cement to clean tubing.
Pulled tubing to 1351' - pumped 330 sxs cement - ran out of cement - had to order more cement.
Pumped 75 sxs cement - good circulation out the 5 1/2" and the 8 5/8".
Pulled tubing out - topped off 5 1/2" with 5 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3214	3519		O.A

INVOICED
DATE 9/9/09
INV. NO. 2010060235


KANSAS CORPORATION COMMISSION
JUL 27 2009

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #3475.

RECEIVED

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

CM 

JUL 23 2009

187

23500001068
2019/10

1871

ROBERT R. PRICE

P.O. BOX 45442

TULSA, OK 74145

#12 CAVE

7-11-18W
C E/2 NW SW

CONTR RANGER DRILLING

CTY ELLIS

GEOL

FIELD COCHRAN WEST

E 1967 KB CM 3/3/81

CARD ISSUED 9/24/81 IP

P 15 BO & 10 BWPD

1962 GL

TOR-LKC 3214-3519
OA

+	+
+	+
+	+
+	+

API 15-051-22,166

SMP	TOPS	DEPTH	DATUM
ANH		1307	+ 660
TARK		2774	- 807
-TOP-		-2970-	--1003-
HEEB		3197	-1230
TOR		3213	-1246
LANS		3236	-1269
B KC		3459	-1492
CONG		3482	-1515
ARB		3580	-1613
RTD		3625	-1658
NO LOG			

8-5/8" 1318/500sx, 5 1/2" 3624/200sx

NO DST'S REPORTED
MICT - CO, PF (TOR-LKC) 3214-3519 OA,
AC 13,500 G (28% HCL), POP, P 15
BO & 10 BWPD, NSG, 5/8/81

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS