

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15486-00-01
Spot: SENENW Sec/Twnshp/Rge: 12-19S-12W
4288 feet from S Section Line, 3076 feet from E Section Line
Lease Name: KULTGEN Well #: 12
County: BARTON Total Vertical Depth: 3371 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	243	0	150 SX
PROD	4.5	3371	0	150 SX

109.56

Well Type: EOR UIC Docket No: E23200.1 Date/Time to Plug: 07/22/2009 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CHARLES SCHMIDT Company: ZENITH DRILLING CORPORATION Phone: (316) 755-3523

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/22/2009 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1550' and 650'.
Ran tubing to 2800' - tied to tubing - pumped 150 sxs cement with 200# hulls.
Pulled tubing to 1550' - pumped 50 sxs cement.
Pulled tubing to 550' - circulated cement to surface with 50 sxs cement.
Pulled tubing - topped off with 10 sxs cement.
Tied to backside - pumped 10 sxs cement.
Max. P.S.I. 300#. Shut in.

Perfs:

Top	Bot	Thru	Comments
3084	3324		

INVOICED
DATE 9/19/09
INV. NO. 2010060234

KANSAS CORPORATION COMMISSION

JUL 27 2009

RECEIVED

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #C33035.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

JUL 23 2009

PR

2550000138
poirip

22.90

ALADDIN & CROWE #12 KULTIGEN "A" 12-19-12W / 53 SE-NE NW

Contr. _____ BARTON County

E 1823 KB Comm. _____ Comp. 6-20-52 IP 190 BOPD.

Tops	Depth	Datum
ANH	650	1173
TOP	2901	=1078
K C	3091	=1271
ARB	3371	=1548
T D	3400	=1577

Casing
 8" 236
 4" 3369

PHY POT.
 DST 2897-2919, 1 HR,
 150' WTRY MUD; SL
 OIL & GAS CUT: BHP
 625#
 DST 3094-3162, 15 MIN,
 190' GAS & SL OIL
 CUT MUD: BHP 590#
 5 GOPH: ACID 2000:
 6 3/4 BOPH

CHEYENNE VIEW POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS