

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20375-00-01
Spot: S2N2SW Sec/Twnshp/Rge: 24-14S-11W
1980 feet from S Section Line, 5165 feet from E Section Line
Lease Name: SEBESTA Well #: 8
County: RUSSELL Total Vertical Depth: 2224 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	265	0	w/300 sxs cmt
PROD	4.5	2224	0	w/150 sxs cmt

Well Type: EOR UIC Docket No: E17954.2 Date/Time to Plug: 07/29/2009 2:30 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perf: 1200' - 507' - 255'.

72.28

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/29/2009 5:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing 1723' - pumped 100 sxs cement with 200# hulls.
Pulled tubing 450' - pumped 80 sxs cement - cement circulated.
POOH. Hooked to casing - pumped 80 sxs cement.
Max. P.S.I. 500#.
Braden head started to circulate - but shut off before cement circulated.
Hooked up to braden head and pumped 40 sxs cement.

Perfs:

RECEIVED
AUG 04 2009
KCC WICHITA

INVOICED
DATE 9/9/09
INV. NO. 2010060233

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #3409.

Plugged through: TBG

District: 04

Signed Ray A Dinkel
(TECHNICIAN)

Form CP-2/3

JUL 31 2009

0.2

235009 06105
9019/10

WILL P. ASH
WICHITA, KS.

#8 SEBASTA

24-14-11W
NW NE SW

Contr. LEBEN DRG., INC.

Cty. RUSSELL

Geol. DICK FOLEY

Pool WILSON CREEK

E. 1675 DF. Cm. 11/2/69 Cp. 12/11/69 IP PMP 80 BOPD +43%

W/TARK-2076-86,
GR 37

API 15-167-20,375

SMP	Tops	Depth	Datum	Csg.
GR H		2072	- 397	8" 265/200 sx; 4 1/2" 2224/100
TARK		2150	- 475	DST 2421-40/3', 875' GIP, 30'
HOW		2352	- 677	O&GCM, BHP 50-50#, FP 50-50#
TOP		2392	- 717	DST 2802-25/3', 125' THIN WM,
WIL CR TOP		2429	- 754	BHP 840-840#/60", FP 60-260#
QH		2592	- 917	DST 2856-79/3', -230' O&GC THIN
HEEB		2678	-1003	WTR DM, BHP 740-650#/60",
TOR		2696	-1021	FP 60-80#
DG		2708	-1033	DST 2880-87/3', 140' MW, BHP
BR LM		2768	-1093	760-760#/45", FP 30-170#
LKC		2784	-1109	PF 20/2076-86 (TARK) FRAC
'30'		2805	-1103	20,000# SD + 585 BW, POP, PMP
RTD		2887	-1212	120 BO + 385 BLW/24 HRS,
				PMP 80 BOPD + 43%W
				NO LOG
				NO CORES

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS