

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21478-00-00
Spot: NESESW Sec/Twnshp/Rge: 6-13S-14W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MCCULLY Well #: 2
County: RUSSELL Total Vertical Depth: 3191 feet

Operator License No.: 4952
Op Name: SCHLOBOHM, STARR F.
Address: 10 GREENLEAF DR
WOLFEBORO, NH 03894

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	380	0	w/unknown sxs cmt
PROD	5.5	3186	0	w/175 sxs cmt

Well Type: OIL UIC Docket No: 4952 Schlobohm, STARR F. Date/Time to Plug: 07/24/2009 3:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS KCC PKT
Proposal Rcvd. from: JOHN DRISCOLL Company: SCHLOBOHM, STARR F. Phone: (785) 483-9580

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 300# hulls.

103.71

Plugging Proposal Received By: CASE MORRIS WitnessType: PARTIAL
Date/Time Plugging Completed: 07/30/2009 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing 840' - pumped 125 sxs cement - cement circulated.
POOH. Hooked to casing - pumped 75 sxs cement with 300# hulls.
Max. P.S.I. 400#. S.I.P. 100#.
07/30/2009 - Hooked to braden head. Max. P.S.I. 200#. (Witnessed)

Perfs:

RECEIVED
AUG 04 2009
KCC WICHITA

INVOICED
DATE 9/9/09
INV. NO. 2010060230

Remarks: ALLIED CEMENTING COMPANY-TICKET #038450.

Plugged through: TBG

District: 04

Signed Ray A Dinkel
(TECHNICIAN)

GEOSON OIL CO., INC.

508 INSURANCE BLDG

WICHITA, KS 67202

CONTR CUSTOM OIL EXPL

#2 MCCULLY

CTY RUSSELL

6-13-14W

NE SE SW

GEOL _____ FIELD SALT CREEK

E 1741 KB CM 6/19/80 CARD ISSUED 2/26/81 IP P 10 BOPD & WTR
LANS 2952-3098 OA

API 15-167-21,478

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
TOP		2634	- 893
HEEB		2860	-1119
TOR		2882	-1141
LANS		2913	-1172
ARB		3181	-1440
RTD		3191	-1450

8-5/8" 380, 5 1/2" 3186/175sx
 DST (1) 2612-2660/30-45-60-90, REC 30' SOCM; SIP 91-149#, FP 22-22/34-34#
 DST (2) 2950-2970/30-45-30-45, REC 60' M, SIP 370-158#, FP 52-52/52-52#
 DST (3) 3044-3110/30-60-60-90, REC 5' O&GCM, 240' GCMW, SIP 283-264#, FP 52-105/135-158#
 DST (4) 3164-3186/30-60-30-60, REC 25' OCM, SIP 1052-0#, FP 52-52/52-52#

0200000000
 01/01/00

(OVER)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

17.0

1725

20/10/00 21855 E

10000