

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01960-00-00
Spot: N2N2NW Sec/Twnshp/Rge: 36-18S-8W
4944 feet from S Section Line, 3973 feet from E Section Line
Lease Name: R J WARNER A Well #: 6
County: RICE Total Vertical Depth: 3192 feet

Operator License No.: 9292
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL
Address: 211 S FRONT ST
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	382		
PROD	7	3187		

103.74

Well Type: OIL UIC Docket No: 31529 Date/Time to Plug: 07/20/2009 9:00 AM
Plug Co. License No.: 9292 Plug Co. Name: MIKE'S TESTING & SALVAGE INC
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/21/2009 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE 1100', 750' 420', AND 250'. RUN TUBING TO 3200' AND PUMP 50 SX'S CEMENT WITH 200#'S COTTON HULLS. PULL TUBING TO 1100' AND PUMP 50 SX'S CEMENT-NO CIRCULATION. PULL TUBING TO 750' AND PUMPED 40 BB'L WATER - NO CIRCULATION. TRIED TO RE-TAG CEMENT AT 1100'-NO PLUG. RUN TUBING BACK DOWN TO 1100' AND PUMP 50 MORE SXS CEMENT WITH CALCIUM CHLORIDE-WAIT 2 HR'S, TRIED TO RE-TAG-NO PLUG. PUMP 50 MORE SX'S CEMENT WITH CALCIUM CHLROIDE - WAIT 2 HR'S AND RE-TAGGED PLUG AT 1000'. PULL TUBING TO 750' AND PUMP 50 SX'S CEMENT-SHUT DOWN FOR DAY. CAME BACK ON 7-21-2009 AND TAGGED CEMENT AT 700'. PULL TUBING TO 420' AND PUMPED 50 SX'S CEMENT - WAIT 1 HR AND TAGGED CEMENT AT 300'. PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT. CONNECTED ON TO ANNULUS AND PUMP 80 SX'S CEMENT - PRESSURED UP TO 300#'S AND SHUT IN. TOPPED OFF 7" WITH 75 MORE SX'S CEMENT - STAYED FULL. USED 465 SX'S CEMENT WITH 350#'S COTTON HULLS.

Perfs:

Top	Bot	Thru	Comments
3187	3192	OH	

INVOICED
DATE 9/4/09
INV. NO 2010060202

KANSAS CORPORATION COMMISSION
JUL 28 2009
RECEIVED

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS. TICKET #5767. COPELAND TICKET #C33032.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PTG