

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

API Well Number: 15-051-23039-00-00  
 Spot: SWSWNE Sec/Twnshp/Rge: 8-13S-18W  
2970 feet from S Section Line, 2310 feet from E Section Line  
 Lease Name: POLIFKA Well #: 3  
 County: ELLIS Total Vertical Depth: 3785 feet

Operator License No.: 6931  
 Op Name: BOWMAN OIL COMPANY, A GENERAL  
 Address: 805 CODELL RD  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3470		
CIBP		3500		
SURF	8.625	166	0	130 SX
T1	2.875	3465		
PROD	5.5	3750	0	130 SX

123.01

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/03/2009 8:00 AM  
 Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
 Proposal Rcvd. from: BILL BOWMAN OR LOUIS Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel. CIBP 3500' and 3470'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
 Date/Time Plugging Completed: 08/03/2009 2:30 PM KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Perforated at 2050' - 1490' - 825'.  
 Ran tubing to 1800' - stacked out - unable to get back thru at 1782'.  
 Quality Oil Well Cementing pumped 50 sxs neat - followed with 300 sxs cement and 450# hulls.  
 Pulled tubing out of hole - waited on more cement.  
 Ran tubing back in - tagged cement at 648'.  
 Quality Oil Well Cementing pumped 135 sxs cement with 450# hulls - lost circulation.  
 Pulled to 320' - pumped 20 sxs cement cwc.  
 PTOH. Topped off with 5 sxs cement.  
 Backside instant pressure 500#.

**Perfs:**

Top	Bot	Thru	Comments
3732			
3690	3691		LAN
3660	3661		
3564	3568		
3540	3544		
3498	3504		LAN
3448	3452		LAN

KANSAS CORPORATION COMMISSION

**AUG 07 2009  
 RECEIVED**

**INVOICED**

DATE 9/14/09  
 INV. NO. 2010060240

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 04

Signed Richard Williams  
 (TECHNICIAN)

CM

**AUG 04 2009**

OK-15-051-23  
 POLIFKA

DREILING RESOURCES 1982 JOINT VENTURE  
 P.O. Box 278 VICTORIA, KS 67671 #3 POLIFKA 8-13-18W  
 CONTR: DREILING OIL, INC. CITY: ELLIS SW SW NE

GEOL: \_\_\_\_\_ FIELD: POL

E 2175 KB CM 6/16/82 CARD ISSUED 8/19/82 IP P 20 BO & 200 BWPD  
 2170 GL SHAW (TOR) 3448-52  
 API 15-051-23,039 (NEW PAY)

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		1469	+ 706
TOP		3178	-1003
HEEB		3427	-1252
TOR		3446	-1271
LKC		3476	-1301
BKC		3707	-1532
CONG		3742	-1567
ARB		NOT REACHED	
RTD&LTD		3785	-1610

8 5/8" 166/130sx; 5 1/2" 3750/530sx  
 DST (1) 3596-3660(LKC)/30-30-10-0,  
 REC 15' M, ISIP 720#, FP 53-53/  
 62-62#  
 MICT - CO, PF (PENN) 1/3732, AC 500G  
 (15% HCL), SWB DWN, NS, PF (LKC)  
 3660-61, 3690-91 w/1 SPF, SWB DWN, NS,  
 NAT, PF (LKC) 3540-44, 3564-68 w/2 SPF  
 AC 500G (15% HCL) FROM 3564-68, SWB  
 DWN, NS, PF (LKC) 3498-3504, AC 3000G  
 (15% HCL), SWB DWN, NS, PF (TOR) 3448-  
 52, w/2 SPF, AC 1000G (15% HCL), SWB  
 DWN w/GSO, POP, P 20 BO & 200 BWPD,  
 (GR 39°), 7/24/82

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS