

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-40066-00-00
Spot: NWSENESE Sec/Twnshp/Rge: 35-26S-5E
1708 feet from S Section Line, 500 feet from E Section Line
Lease Name: BISAGNO Well #: 4
County: BUTLER Total Vertical Depth: 2724 feet

Operator License No.: 6655
Op Name: CRAWFORD, GARRY F. DBA CRAWFO
Address: PO BOX 727
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	205		125 SX 88.53
PROD	6.625	2650		LEFT CASING IN HOLE

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/11/2009 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: BRANCE CRAWFORD Company: CRAWFORD PRODUCTION CO Phone: (316) 323-5513

Proposed Plugging Method: SAND BACK 50' ABOVE OPEN HOLE, AND CAP WITH 7 SXS, SQUEEZE HOLES @ 250' AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 06/11/2009 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH TUBING @ 2,400', ESTABLISHED CIRCULATION AND CONSOLIDATED OIL WELL SERVICE MIXED & PUMPED 35 SXS CLASS A 3% CC AND DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2,115'. SWEDGED INTO 6-5/8" AND CONSOLIDATED MIXED & PUMPED 35 SXS CLASS A 3% CC AND DISPLACED IN CASING W/RUBBER PLUG. WAITED 2 HOURS, TAGGED CEMENT @ 260'. PERFORATED SQUEEZE HOLE @ 250'. ESTABLISHED CIRCULATION AND CONSOLIDATED MIXED & PUMPED 180 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 P.M., 6-11-2009. CONSOLIDATED CEMENT TICKET #20937.

Perfs:

Top	Bot	Thru	Comments
2650	2724	OH	

KANSAS CORPORATION COMMISSION
AUG 12 2009
RECEIVED
INVOICED

Remarks:

Plugged through: TBG

DATE 9/14/09
INV. NO. 2010060242

District: 02

Signed Duane Krueger
(TECHNICIAN)