

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20200-00-00
Spot: SWSENE Sec/Twnshp/Rge: 22-17S-27W
2310 feet from N Section Line, 990 feet from E Section Line
Lease Name: MERRITT C ATWELL Well #: 2
County: LANE Total Vertical Depth: 4270 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-------------------------------|
| SURF | 8.625 | 319 | | WITH 250 SX CMT |
| DVT | | 2012 | | WITH 460 SX CMT 138.78 |
| PROD | 4.5 | 4271 | 0 | WITH 660 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/08/2009 10:30 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: STEVE BODINE Company: DAYSTAR PETROLEUM Phone: (316) 755-3492

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT AT 4122'. RIH W/TBG TO 2020'. FILL WITH CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/08/2009 5:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4000' & PUMP 25 SX CMT & 200# HULLS. PULLED TBG TO 2020' & PUMPED 160 SX CMT. LOST CIRCULATION. PULLED TBG. WAITED 3 HOURS. TOC @ 450'. FILLED CASING WITH 40 SX CMT. 7/13/09" CUT-OFF HEAD. COULD SEE CMT IN CASING.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4228 | 4231 | | |
| 4182 | 4186 | | |
| 4149 | 4151 | | |
| 4122 | 4128 | | |

INVOICED
DATE 9/14/09
INV. NO. 2010060243

KANSAS CORPORATION COMMISSION
AUG 07 2009
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
JUL 29 2009 *NR*

KCC DODGE CITY

Form CP-2/3
[Signature]