

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22179-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 15-16S-28W
1140 feet from S Section Line, 2575 feet from E Section Line
Lease Name: LAWRENCE UNIT Well #: 34-15
County: LANE Total Vertical Depth: 4500 feet

Operator License No.: 34038
Op Name: FLATIRONS RESOURCES LLC
Address: 303 E 17TH AVE STE 940
DENVER, CO 80202

String Size Depth (ft) Pulled (ft) Comments
SURF 8.625 252 WITH 175 SX CMT

146.25

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/17/2009 4:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: DUSTY RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2010' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 280' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 07/17/2009 6:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 2010' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 280' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

INVOICED
DATE 9/14/09
INV. NO. 2010060245

KANSAS CORPORATION COMMISSION

AUG 07 2009
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
JUL 29 2009
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)