

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-19032-00-01
Spot: SWNW Sec/Twnshp/Rge: 28-29S-6W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease Name: GRABER Well #: 1-28 RE
County: KINGMAN Total Vertical Depth: 4545 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	269		200 SX CMT.
PROD	5.5	4514	2640	370 SX <u>147.71</u>

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/04/2009 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 4066' AND CAP WITH 5 SKS OF CMT. RECOVER CASING. SPOT 35 SKS PLUGS AT 1050, 650', AND CIRC CMT FROM 320-0.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 08/04/2009 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE SANDED OFF TO 4000', AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 2640' AND PULLED TO 1050', WHERE 35 SKS OF CMT WAS SPOTTED IN PLACE. THE CASING WAS PULLED TO 650', WHERE 35 SKS OF CMT WAS SPOTTED IN PLACE. THE CASING WAS PULLED TO 320', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4116	4128	CSG	

KANSAS CORPORATION COMMISSION
AUG 12 2009
RECEIVED

NVOICED
DATE 9/14/09
INV. NO. 2010060249

Remarks: QUALITY OIL WELL CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed 
(TECHNICIAN)