

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03199-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 13-15S-18W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: LEIKER T S TWIN TO 2 Well #: 9
County: ELLIS Total Vertical Depth: 3613 feet

Operator License No.: 30762
Op Name: OIL COMPANY OF AMERICA, INC.
Address: 1200 MAIN STE 101
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1168	0	570 SX
PROD	5.5	3612	2009	150 SX

117.42

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/05/2009 11:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: ROGER MOSES Company: OIL COMPANY OF AMERICA, INC. Phone: (786) 623-6771

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 300# hulls.
High fluid level.
Large hole in casing at 2000'. Found on pulled casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/05/2009 6:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Professional Pulling Services sanded off bottom to 3100' and topped with 5 sxs cement.
Perf Tech shot casing at 2200'. Casing would not come loose.
Re-shot casing at 2009'. Professional Pulling pulled casing to 1689'.
Allied rigged to casing and pumped 150 sxs cement with 200# hulls mixed in.
Pulled casing to 1175'. Allied rigged to casing and pumped 40 sxs cement with 100# hulls.
Pulled casing to 550'. Allied rigged to casing and pumped 40 sxs cement.
Pulled casing to 150'. Allied rigged to casing and pumped 45 sxs cement to circulate cement to pit.
Pulled casing - hole standing full.

Perfs:

Top	Bot	Thru	Comments
3554	3566		
3438	3475		
3306	3330		

KANSAS CORPORATION COMMISSION

AUG 12 2009

RECEIVED

INVOICED

DATE

9/14/09


Remarks: ALLIED CEMENTING COMPANY-TICKET #36324.

INV. NO. 2010060254

Plugged through: CSG

District: 04

Signed


(TECHNICIAN)

CM

2017RB
POLYMER
2017RB

13-15-18W

ALPINE OIL & ROYALTY

#9 T S LEIKER SW NW NW
(TWIN TO #2)

Contr. QUAKER DRLG ELLIS County

E 2017RB Comm. Comp. 5-4-56 IP 438 BOPD/LANS

Tops	Depth	Datum
ANH	1158	859
HEEB	3248	-1231
LANS	3294	-1277
CONG	3567	-1550
ARB	3611	-1594
TD	3613	-1596

Casing
 8" 1168
 5" 3612
 DST 3306-30/1 HR, 1470' FRGY
 OIL, BHP 500#
 DST 3438-75/1 HR, 122' V HO
 & GCM, BHP 400#:
 PERF 106/3454-66: 3472-78
 ACID 2000: 350' OIH: SWB
 25 BOPH/6 HR:
 LEIKER EAST

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

WV 11 11