

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-20796-00-01  
Spot: NWNWSW Sec/Twnshp/Rge: 17-31S-18W  
2298 feet from S Section Line, 5008 feet from E Section Line  
Lease Name: BURKHALL Well #: 1  
County: COMANCHE Total Vertical Depth: 5265 feet

Operator License No.: 5893  
Op Name: PRATT WELL SERVICE, INC.  
Address: PO BOX 847  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4950		WITH 2 SX CMT 171.11
SURF	8.625	663		WITH 320 SX CMT
PKR		4981		PACKER TYPE AND SETTING DEPTH: COATED LOCKSET @4981'
PROD	5.5	5252	2100	WITH 125 SX CMT

Well Type: EOR UIC Docket No: E28889.1 Date/Time to Plug: 07/27/2009 9:15 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 770-0995

Proposed Plugging Method: SET CIBP @ 4950' WITH 2 SX CMT. PLUG AT 1160' WITH 15 SX GEL & 50 SX CMT. PLUG AT 690' WITH 50 SX CMT. PLUG AT 340' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/27/2009 11:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4950' WITH 2 SX CMT. 1ST PLUG AT 1167' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 677' WITH 50 SX CMT. 3RD PLUG AT 338' WITH 30 SX CMT. 4TH PLUG AT 35' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5149	5153		
4996	4999		

KANSAS CORPORATION COMMISSION

AUG 07 2009

RECEIVED

INVOICED

DATE 9/14/09

INV. NO. 2010060254

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED  
JUL 28 2009  
KCC DODGE CITY

Signed Eric MacLaren  
(TECHNICIAN)