

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5446
Name: BEN GILES
Address 1: 532 SOUTH MARKET
Address 2: _____
City: WICHITA State: KS Zip: 67202 + _____
Contact Person: BEN GILES
Phone: (316) 265-1992

API No. 15 - 173-20833-00-01
If pre 1967, supply original completion date: _____
Spot Description: 7
35N, APPRX C N/2, NW Sec. 12 Twp. 26 S. R. 2 East West
sw ne nw
320 943 Feet from North / South Line of Section
1320 1775 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: SEDGWICK
Lease Name: HLADIK Well #: 1

KCC REC'D
9/3/09

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: D-28439.0 ENHR Permit #: _____ Gas Storage Permit #: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8 Set at: 200 Cemented with: 100 Sacks
Production Casing Size: 5 1/2 Set at: 3202 Cemented with: 150 Sacks

List (ALL) Perforations and Bridge Plug Sets:
HUNTON 3136-38
MISSISSIPPI 2825-28
Elevation: 1329 (G.L. / K.B.) T.D.: _____ PBTD: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

IN ACCORDANCE WITH KCC SPECIFICATIONS AND REGULATIONS

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No
If ACO-1 not filed, explain why:

RECEIVED
SEP 14 2009
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: TOM SCHMIDT &/OR BEN GILES
Address: 532 SOUTH MARKET City: WICHITA State: KS Zip: 67202 + _____
Phone: (316) 265-1992
Plugging Contractor License #: 34231 Name: M & S WELL SERVICE, LLC
Address 1: 532 SOUTH MARKET Address 2: _____
City: WICHITA State: KS Zip: 67202 + _____
Phone: (316) 295-4355
Proposed Date of Plugging (if known): 09/31/09

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 9-14-09 Authorized Operator / Agent: Ben Giles Operator
(Signature)

Dated 9/14/09
BEG

WALNUT VALLEY OIL INC
150 S ROCK RD
WICHITA, KS 67207
CONTR ASPEN OIL INC

#1 HLADIK 35'N, APPX C N/2 NW
12-26-2E
CTY SEDGWICK

GEOL _____ FIELD GREENWICH

1335 KB CN 7/21/80 CARD ISSUED 10/9/80 IS P 10 BOPD
1329 GL

+	+	+
+	+	+
+	+	+

API (15-173-20,259)

MISS 2825-28
HUNT 3136-38

SMP	TOPS	DEPTH	DATUM
KC LM	2340	-1005	
B KC	2504	-1172	
MISS LM	2782	-1447	
MISS GHT	2817	-1482	
B MISS	2949	-1614	
KIND SH	3086	-1751	
HUNT	3130	-1795	
SIMP	3181	-1846	
RTD	3200	-1865	

8-5/8" 200, 5 1/2" 3202/150sx

DST (1) 2810-2829 (MISS)/35-30-60-30,
REC 120' GIP, REC 991' HOCM
(AVG 50% O, 15% WTR), 812' MW&SW,
SIP 691-698#, FP 71-315/380-887#,
HP 1512-1500#

DST (2) 3130-3136 (HUNT)/30-30-60-36,
REC 20' CL O, 185' HOCM (AVG 80% O)
45' MW, SIP 1157-1159#, FP 31-32/
73-75#, HP 1626-1597#

MIC - CO, PF (HUNT) 2/3136-39, TST
80, NAT, PF (MISS) 3/2825-28, TST 80,
NAT, POP, COMMINGLED.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED

SEP 14 2009

KCC WICHITA



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

GILES, BENJAMIN M.
532 S MARKET
WICHITA, KS 67202-3906

September 17, 2009

Re: HLADIK #1
API 15-173-20833-00-01
12-26S-2E, 4337 FSL 3505 FEL
SEDGWICK COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after March 16, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000