

**AFFIDAVIT OF COMPLETION FORM**

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: (Oil), gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. X Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR R.A. Comeau  
LIBERTY ENTERPRISES, INC

API NO. 15-163-21,351-0000

ADDRESS 308 West Mill  
Plainville, Kansas 67663

COUNTY Rooks

FIELD Lynd South Field

\*\*CONTACT PERSON Charles G. Comeau  
PHONE 913-434-4686

PROD. FORMATION Arbuckle

LEASE Francis Collins

PURCHASER CRA, Inc.

WELL NO. #1


ADDRESS P.O. Box 7305  
Kansas City, Missouri

WELL LOCATION SE NW NE

990 Ft. from North Line and  
1650 Ft. from East Line of  
the NE/4 SEC. 9 TWP. 10S RGE. 19W

DRILLING PIONEER DRILLING COMPANY, INC.  
CONTRACTOR  
ADDRESS 308 West Mill  
Plainville, Kansas 67663

PLUGGING  
CONTRACTOR  
ADDRESS



WELL PLAT

KCC   
KGS   
MISC   
(Office Use)

TOTAL DEPTH 3772' PBDT 3542'

SPUD DATE 8/9/81 DATE COMPLETED 9/4/81

ELEV: GR 2181' DF 2184' KB 2186'

DRILLED WITH (CABLE) (ROTARY) (NEW) TOOLS (New) / (USED) casing.

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	260'	Common	145	2% gel, 3% cc
Production	7 7/8"	5 1/2"	14#	3765'	ASC	150	

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4 per ft.		3718-19'
<b>TUBING RECORD</b>			4 per ft.		3715-16'
Size	Setting depth	Packer set at			
2 1/2"	3538'				

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
	11-24-81

Date of first production 9/4/81 Producing method (flowing, pumping, gas lift, etc.) Pumping unit Gravity 24°

RATE OF PRODUCTION PER 24 HOURS  
Oil 24 bbls. Gas 43% MCF Water 18 bbls. Gas-oil ratio 0.18

Disposition of gas (vented, used on lease or sold) \_\_\_\_\_ Perforations \_\_\_\_\_

\*\*The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum \_\_\_\_\_ Depth 150'

Estimated height of cement behind Surface Pipe cement circulated.

DV USED? None

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
	0'	70'		
sands and shale	70'	260'		
sand and shale	260'	1162'		
sand and shale	1162'	1548'		
anhydrite	1548'	1593'		
sand and shale	1593'	1665'		
shales and limes	1665'	2140'		
shales and lime	2140'	2287'		
shale and lime	2287'	2500'		
shales and lime	2500'	2738'		
shale and lime	2738'	2944'		
shales and lime	2944'	3147'		
limes and shales	3147'	3175'	Topeka	3150'
limes and shales	3175'	3275'	Heebner	3360'
lime and shales	3275'	3394'	Toronto	3385'
lime and shale	3394'	3467'	Lansing/KC	3401'
lime and shale and chert	3467'	3480'		
lime and shale	3480'	3540'		
lime and shale	3540'	3588'		
lime and shales	3588'	3673'	Base/KC	3613'
lime and shale	3673'	3680'		
lime and shale	3680'	3707'		
lime and shale	3707'	3722'	Arbuckle	3714'
arbuckle	3722'	3772'		
	3772'	RTD		

AFFIDAVIT

STATE OF KANSAS, COUNTY OF ROOKS SS,

Charles G. Comeau OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Secretary-Treasurer (FOR)(OF) LIBERTY ENTERPRISES, INC.

OPERATOR OF THE Francis Collins LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON


SAID LEASE HAS BEEN COMPLETED AS OF THE 4th DAY OF September, 1981, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.


FURTHER AFFIANT SAITH NOT.

(S)   
Charles G. Comeau

SUBSCRIBED AND SWORN BEFORE ME THIS 20<sup>th</sup> DAY OF November 1981



MY COMMISSION EXPIRES:

  
NOTARY PUBLIC  
Sharon Garvert