

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20389-00-00
Spot: E2NESW Sec/Twnshp/Rge: 24-14S-11W
1980 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SEBESTA Well #: 9
County: RUSSELL Total Vertical Depth: 2915 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	289	0	175 SX
PROD	4.5	2914	0	165 SX

94.74

Well Type: EOR UIC Docket No: E15539.1 Date/Time to Plug: 08/06/2009 10:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perf Tech shot two hole perms at 1200' - 507' - 275'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/06/2009 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Klima Well Service RIH with tubing to 2800'.
Quality Oil Well Cementing rigged to tubing - pumped 100 sxs cement wit 300# hulls mixed in.
Pulled tubing to 1300'. Quality rigged to tubing - pumped 60 sxs cement with 200# hulls to circulate cement up 4 1/2" casing.
Shut in 4 1/2" casing - pumped an additional 70 sxs cement to circulate cement up 8 5/8" casing. Shut in 8 5/8" casing.
Pulled tubing - rigged to 4 1/2" casing with a swedge and pumped 30 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
2886	2889		
2810	2828		

KANSAS CORPORATION COMMISSION


**AUG 12 2009
RECEIVED**

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3414.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

AUG 07 2009

WILL P. ASH
WICHITA, KANSAS
CONTR SAGE DRILLING CO.

"TWIN" 24-14-11W
#9 SEBESTA APP E/2 NE SW
CTY RUSSELL

GEOL

FIELD WILSON CREEK

E 1680 KB CM 1/2/70 ^{CARD}ISSUED 5/28/70 IP WIW/LKC 2810-28

API 15-167-20,389

SMP	TOPS	DEPTH	DATUM	
			8 5/8" 289/175SX; 4 1/2" 2914/165SX	
GR H	2070	- 390		CORE (TARK) REC 18'SH-VF SD STRKS
TOP	2429	- 749		
HEEB	2679	- 999		DST(1) 2803-27/3', 180'GIP, 40'CGO, 40'
TOR	2700	-1020		HOCM, 40'M, BHP 600-585#/60", FP
BR LM	2772	-1092		80-160#
LKC	2789	-1109		DST(2) 2876-86/3', 15'OIL, 240'THIN
RTD	2915	-1235		OILY MW, BHP 750-750#/60", FP 30-220#

MICT-PF 16/2810-28 AC 250MCA + 3000
RET AC SWB 15 BOPH, POP, P 60-70BOPD,
OIL DECL TO BE WIPW

NO LOG

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS