

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

03

API Well Number: 15-163-00271-00-02
Spot: SENWSE Sec/Twnshp/Rge: 28-8S-17W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: STAMPER Well #: 3-28
County: ROOKS Total Vertical Depth: 3539 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1328	0	w/650 sxs cmt
PROD	4.5	3528	0	w/200 sxs cmt <u>115.02</u>

Well Type: SWD Oil | *KCC PEST per CP2/3* UIC Docket No: D20140.0 Date/Time to Plug: 07/29/2009 10:30 AM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (316) 265-3311

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls.
Perforated at 1750' - 1325' -550'.
Casing patch at 2730'.
Note: Docket withdrawn 03/03/1982 - completed as a producing well.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/29/2009 1:40 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2753' - pumped 60 sxs 60/40 pozmix - 4% gel with 150# hulls.
Pulled tubing to 1835' - pumped 60 sxs 60/40 pozmix - 4% gel with 150# hulls.
Pulled tubing to 914' - pumped 60 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing and hooked onto 4 1/2" casing.
Pumped 105 sxs 60/40 pozmix - 4% gel to circulate 8 5/8" to surface.
Shut 8 5/8" and pumped 15 sxs 60/40 pozmix - 4% gel.
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3161	3327		

KANSAS CORPORATION COMMISSION
AUG 12 2009
RECEIVED

INVOICED
DATE: 9/14/09
NO. 2010060239

Remarks: ALLIED CEMENTING COMPANY-TICKET #38455.

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

AUG 05 2009

PKT

