

4-060879

15-167-20274-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

S-20

API Number: 15- - 1969

S2 SW NW /4 SEC. 34, 12 S, 15 W
2970 feet from S section line
4620 feet from E section line

Operator license# 6772

Lease: Meckel Well # 1

Operator: V. Francis Weigel Family Ptr.

County: Russell

Address: P.O. Box 219
Gorham, Kansas 67640

Well total depth 3206 ^{104.19} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 253 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 1:30 P.M. Day: 20 Month: May Year: 1996

Plugging proposal received from: Mike Kelso/Richard

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 250 sxs 60/40 posmix - 10% gel and hulls.
Open to T.D. with F.L. below 2000' confirmed by wireline.

RECEIVED
KANSAS CORPORATION COMMISSION

5-30-1996
MAY 30 1996

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None

Completed: Hour: 3:45 P.M. Day: 20 Month: May Year: 1996

Actual plugging report: 8 5/8" to 253'. 5 1/2" to 3206' w/150 sxs. Squeezed holes at 379' w/175 sxs. Shot casing at 1550' and well started venting gas. Shot casing at 910' and well started venting mud, debris and gas. Well blew down and was capped with cementing swedge and valve. Well built pressure to 550# pressure prior to commencement of plugging. Tied onto annulus with instant 500# S.I.P. Tied onto production casing and pumped 250 sxs cement with 500# hulls. Max. P.S.I. 1000#. S.I.P. 500#. Check cement top 2 days later. okay.


Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 1745 GL

I did did not observe the plugging.

 (agent)

AK

Form CP-2/3

INVOICED

JUN 12 1996

DATE

INV. NO. 45784