

1 020233

Amended

093-20599-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 2/18/79

C NW NE, SEC. 13, T 21 S, R 35 W/R

4620 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6593

Operator: Coastal Oil & Gas Corporation Inc
Name: 6363 Woodward Dr St 350
Address: 211 North Robinson, Suite 1700
Oklahoma City, OK 73102
Houston TX 77057

Lease Name unruh Well # h3 KCCPKT
County Kearny Per ACOI

Well Total Depth 4950 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 528

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Coastal Oil & Gas Corporation License Number 6593

Address 211 North Robinson, Suite 1700, Oklahoma City, OK 73102

Company to plug at: Hour: 10:15 a.m. Day: 15 Month: 6 Year: 19 89

Plugging proposal received from C. Brad Crouch

(company name) Coastal Oil & Gas Corporation (phone) 405-239-7031

were: 5 1/2" at 4943' Perfs at 4837-4846' Elevation 3070.8' GL Pipe scraper & bit in hole

1st plug pump 5 sx hulls and 150 sx Econolite down 5 1/2",

2nd plug pump 110 sx cement down annulus.

KANSAS CORPORATION COMMISSION
AUG 10 2009
RECEIVED

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 p.m. Day: 15 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug ran 4 sx hulls and 300 sx econolite 65/35 Pozmix down 5 1/2", pressured to 400 psi, shut in, held pressure.

2nd plug ran 1 sx hulls mixed in lead cement down annulus, ran 130 sx Class H cement.

Pumped in at 80 psi pressure. Pressured to 300#. Shut down, held pressure.

Remarks: Used Econolite 65/35 Pozmix and Class H cement by Dowell-Schlumberger. No casing recovery.
(if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed [Signature]
(TECHNICIAN)