

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21994-00-00
Spot: SWSNW Sec/Twnshp/Rge: 25-33S-4E
3007 feet from S Section Line, 3636 feet from E Section Line
Lease Name: MOSLER Well #: 2
County: COWLEY Total Vertical Depth: 3090 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	188		65 SXS CMT
PROD	4.5	3084		

100.43

Well Type: SWD UIC Docket No: _____ Date/Time to Plug: 04/13/2009 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY ANSTINE Company: ANSTINE & MUSGROVE Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 04/13/2009 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH SET CIBP @ 1871'. RIH W/TBG @ 1870', CONSOLIDATED MIXED & PUMPED 10 SXS 60/40 POZMIX 4% GEL AND DISPLACED IN CASING. TESTED CASING @ 100#, HELD OK. SHOT SQUEEZE HOLES @ 300', SWEDGED INTO 4-1/2" CASING, ESTABLISHED CIRCULATION, CONSOLIDATED MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENTING TICKET #20565.

Perfs:

Top	Bot	Thru	Comments
1907	1944	CSG	

INVOICED
9/9/09
2010060224

KANSAS CORPORATION COMMISSION
MAY 08 2009
RECEIVED

Remarks: DOCKET #D-21,634

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

JK

OK